

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21007-00-01  
Spot: NWSESE Sec/Twnshp/Rge: 19-9S-19W  
820 feet from S Section Line, 990 feet from E Section Line  
Lease Name: MARCOTTE Well #: 1  
County: ROOKS Total Vertical Depth: 3581 feet

Operator License No.: 6484  
Op Name: ANDERSON ENERGY, INC.  
Address: 221 S. BROADWAY, SUITE 302  
WICHITA, KS 67202

CIBP Size: feet: 3563  
PROD Size: 5.5 feet: 3579 100 SX CMT  
SURF Size: 8.625 feet: 257 180 SX CMT

# 116 38

Well Type: OIL UIC Docket No: Date/Time to Plug: 08/31/2004 1:00 PM  
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
Proposal Rcvd. from: GARY WAGNER Company: ANDERSON ENERGY, INC. Phone: (785) 735-4412

Proposed Plugging Method: Ordered 320 sxs 60/40 pozmix - 10% gel - 600# hulls.  
TOF at 2000'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/31/2004 3:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Pumped down 5 1/2" casing with 310 sxs cement with 600# hulls.  
Max. P.S.I. 300#. S.I.P. 100#.  
8 5/8" - 10 sxs cement at 300# P.S.I.

Perfs:

Top	Bot	Thru	Comments
3509	3511		
3500	3503		
3423	3425		
3406	3408		
3329	3332		
3312	3314		

Remarks: SWIFT SERVICES, INC.

Plugged through: CSG

District: 04

Signed Dennis L. Hamel  
(TECHNICIAN)

INVOICED

DATE 9-14-04  
REF. NO. 2005060524

Form CP-2/3

SEP 08 2004

THORNTON E ANDERSON  
 THREE PARK CENTRAL SUITE 1055 #1 MARCOTTE 19-9-19W  
 DENVER, COLO 80202 170' S, NW SE SE  
 CONTR ABERCROMBIE DRILLING CTY ROOKS

GEOL \_\_\_\_\_ FIELD GICK

E 2136 KB CM 12/8/79 CARD ISSUED 4/24/80 IP P 117 BOPD & 5 BWPD  
 API 15-163-21,007 ARB OH 3579-3581

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
*ANH		1541	+ 595
*B ANH		1580	+ 556
TOP		3082	- 946
HEEB		3288	-1152
LANS		3328	-1192
*ARB		3578	-1442
LTD		3578	-1442
RTD		3580	-1444
DDTD		3581	-1445
*SAMPLE TOPS			

8-5/8" 257/180sx, 5 1/2" 3579/100sx  
 NO DST'S  
 MICT - CO, DD TO 3581', (ARB OH), AC  
 1000 GAL, POP, P 117 BOPD & 5 BWPD

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

MARCO