

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21195-00-00
Spot: SENENE Sec/Twnshp/Rge: 21-15S-18W
4290 feet from S Section Line, 430 feet from E Section Line
Lease Name: ENGEL Well #: 4
County: ELLIS Total Vertical Depth: 3625 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

PROD Size: 5.5 feet: 3624 175 SX CMT
SURF Size: 8.625 feet: 1181 450 SX CMT

\$117⁸¹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2004 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered 250 sxs cement and 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/27/2004 11:00 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Sanded wellbore from 3625' to 3130' and 5 sxs cement.
Shot casing off at 2220' and pulled 12 joints to 1850'.
At 1850' - spotted 120 sxs cement and 300# hulls.
Pulled to 1200' - spotted 40 sxs cement and 100# hulls.
Pulled to 500' - spotted 30 sxs cement and 100# hulls.
Pulled to 200' and circulated 40 sxs cement - cellar full.
Pulled all casing and cellar still full.
Total of 230 sxs 60/40 pozmix and 500# hulls.

Perfs:

Top	Bot	Thru	Comments
3196	3496		

RECEIVED
SEP 13 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Roger L. Moses
(TECHNICIAN)

INVOICED


DATE 9-14-04
NO. 2005060528

SEP 08 2004

IMAGED

LIBERTY ENTERPRISES, INC. REPLACEMENT CARD 21-15-18W
 308 W. MILL #4 ENGEL 100'W,
 PLAINVILLE, KS 67663
 CONTR C & G DRILLING COMPANY CITY ELLIS C SE NE NE
 GEOL BILL SLADEK FIELD SCHOENCHEN

ELV 2021 KB SPD 6/30/76 CARD ISSUED 8/19/76 IP P 25 BOPD, TR WTR
 API 15-051-21,195 LKC 3321-3395 OA



LOG	Tops	Depth/Datum	
			8 5/8 " 1181; 5 1/2 " 3624
			DST (1) 3249-78 (TOR) / 30-30-30-30, REC 20' THIN M, SIP 810-522#, FP NA.
			DST (2) 3308-30 (LKC) / 30-30-30-30, REC 360' HOCM, 480' MO, SIP 477-472#, FP NA
TOP	2988	967	
HEEB	3250	1229	
TOR	3269	1248	DST (3) 3358-98 (LKC) / 30-30-30-30, REC 130' OIL & GCM, 240' VHO & GCM, 280' VHOCM, W / FREE OIL, ISIP NA - FSIP 884#, FP NA
LKC	3298	1277	
BKC	3538	1517	
ARB	3611	1590	DST (4) 3410-78 (LKC) / 30-30-30-30, 60' GIP, REC 40' HOCM, 120' HOCM, W / FREE OIL, SIP 216-915#, FP NA
RTD	3625	1604	
			DST (5) 3613-25 (ARB) / 30-30-30-30, REC 186' OCSW, SIP 1164-1108#, FP NA
			MICT - CO, PF (LKC) 3391-95, 1 / 3341-45, 1 / 3329-32, 1 / 3321-24, AC 5000G, SWB DWN, SO, POP, P 22-25 BOPD, TR WTR

CORRECTION: 9/8/83 - ORIGINALLY FIRST REPORTED IN C S/2 NE NE NE

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS