

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21561-00-00
Spot: SENENWSE Sec/Twnshp/Rge: 31-11S-19W
2190 feet from S Section Line, 1450 feet from E Section Line
Lease Name: SOLOMON A P Well #: 6
County: ELLIS Total Vertical Depth: 3744 feet

Operator License No.: 4767
Op Name: RITCHIE EXPLORATION, INC.
Address: BOX 783188 8100 E 22ND ST. N. #700
WICHITA, KS 67278

CIBP Size: feet: 3532
CIBP Size: feet: 3716
PROD Size: 4.5 feet: 3743 175 SX CMT
SURF Size: 8.625 feet: 167 125 SX CMT

#12168

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/07/2004 10:30 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: PETER FIORINI Company: RITCHIE EXPLORATION, INC. Phone: (785) 628-2715

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/07/2004 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech RIH and shot three 2-shot perfs at 800' - 1525' and 2025'.
Express Well Service RIH with tubing to 2017'.
Allied rigged onto tubing and pumped 50 sxs cement with 300# hulls mixed in.
Pulled tubing to 1025' - pumped 110 sxs 60/40 pozmix with 200# hulls to circulate cement to surface.
Pulled tubing - tied onto 4 1/2" casing with a swedge and pumped 80 sxs 60/40 pozmix with 50# hulls mixed in.
Max. P.S.I. 450#. S.I.P. 200#.
Tied onto backside - pumped 35 sxs 60/40 pozmix with 50# hulls mixed in.
Max. P.S.I. 300#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3741	3761		
3594	3598		
3558	3562		

Remarks: LEASE NAME WAS CHANGED-ORIGINALLY KNOWN AS SOLOMON DALE #6-31. ALLIED CEMENTING COMPANY-TICKET #16063.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

NO
INVOICED

DATE: 9-14-04

INV NO: 2005060529

Form CP-2/3

SEP 09 2004

0916

INDEXED

DON E. PRATT
P.O. BOX 370
HAYS, KS. 67601

#6-31 DALE SOLOMON

31-11-19W
450' FNL &
1450' FEL SE

CONTR MURFIN DRILG. CO. CTY ELLIS

GEOL _____ FIELD STAR EXT (1/4 N)

E 2140 KB CM 9/26/78 CARD ISSUED 11/9/78 IP P 40 B0 & 40 BWPD
LKC 3469-73

API 15-051-21,561

+	+	+
+	+	+
+	+	+

LOG	TOPS	DEPTH	DATUM
TOP		3156	-1016
HEEB		3379	-1239
TOR		3401	-1261
LKC		3419	-1279
B KC		3643	-1503
WEA ARB		3730	-1590
RTD		3744	-1604

8-5/8" 167/125 sx; 4 1/2" 3743/175 SX
DST (1) 3376-3441/20-30, 15' M, FSIP
193#; FP 65-65#
DST (2) 3435-85/30-30-30-30, 270' GIP,
1300' OCW, SIP 1213-1136#; FP 129-
643#
DST (3) 3480-3515/30-30-30-30, 1735'
G & SOCW, SIP 739-801#; FP 130-
710#
DST (4) 3535-3605/30-30-30-30, 930' SW,
SIP 1097-645#; FP 129-387#
DST (5) 3641-3734/30-30, 15' M, FSIP
478#; FFP 129#
MICT - CO, PF (LKC) 3469-73, AC 1000,
SWB 9.28 BFPH, 50% O, POP, P 40 B0 &
40 BWPD

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS