



JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1963
17-1-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Albert Unruh of Southwest Csg. Pulling Inc. has this

date requested permission to plug the following described well:

Herman George Kaiser

Mr. Unruh guarantees payment of the plugging fee.

Operator's full Name: Herman George Kaiser,

Complete Address: 909 Palace Building, Tulsa, Oklahoma.

Lease Name: Reub Well No. 1

Location: CSE-NE Sec. 13 Twp. 18 Rge. (E) (W) 42

County Cheyenne Total Depth 5513 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Unruh was instructed to plug the well as follows:

240' -- 10 3/4 Surface pipe, cement circulated.

4750' -- 5 1/2", cemented with 175 Sx Poz-Mix.

Top of perforations @ 4537'. Plugged back to 4590'.

Sand well back to 4525' and set 5 Sx cement with dump bailer.

Pull 5 1/2" to 600', and displace 20 Sx cement thru casing. Pull
5 1/2" to 225' and displace 20 Sx cement thru Casing. Pull 5 1/2"
set bridge @ 35' and 10 Sx cement. Very truly yours,

H. L. Tschel
Conservation Division Agent