

10 ~ KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-023-1-00-00
19003

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 1 1963
7-1-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Herman George Kaiser,

Complete Address: 909 Palace Building, Tulsa, Oklahoma.

Lease Name Reub Well No. 1

Location CSE-NE Sec. 13 Twp. 13 Rge. 3 (E) 4 (W) 2

County Cheyenne Total Depth 5513

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Co. Inc.,

Address: Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 1:15PM Day 25 Month 6 Year 1963

The Above well was plugged as follows:

240'--10 3/4" Surface Pipe, cement circulated. 5 1/2" set @ 4750', cemented
with 175 Sx Poz-Mix. Perforated from 4537' to 4543'. Plugged back to 4590'.
Sanded well back to 4525' and set 5 Sx cement with dump bailer. Pulled 5 1/2"
to 600' and circulated heavy gel mud. (15 Sx Gel). Displaced 20 Sx cement
thru casing @ 600'. Pulled 5 1/2" to 225' and displaced 20 Sx cement thru 5 1/2".
Pulled 5 1/2", set bridge @ 35' and 10 Sx cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor