

KANSAS

Y
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 7 1973

CONSERVATION DIVISION
Wichita, Kansas
3-7-73

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-153-20149-00-00

Operator's Full Name Pickrell Drilling Company,

Complete Address 704 Fourth National Bank Building, Wichita, Kansas.

Lease Name Hubbard Well No. A-1

Location App: CNW-SW Sec. 28 Twp. 3 Rge. (E) (W) 36

County Rawlins Total Depth 4520'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Pickrell Drilling Company,

Address Above License No.

Operation Completed: Hour 1:00 AM Day 5 Month 3 Year 1973

The above well was plugged as follows:

361'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 2100'. Landowner Has requested well be left open in surface casing to be developed as a fresh water well.

Circulated hole with heavy mud. Pulled DP to 2325' and displaced 110 Cu. Ft. cement thru DP from 2325' to 2000'. Pulled DP to 370' and displaced 30 Cu. Ft. cement thru DP from 370' to 300'. Pulled DP to 310' and circulated clear water in well. Left top open.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichols*
Well Plugging Supervisor

DATE 3/7/73
INV. NO. 7109-u