

RECEIVED  
SEP 16 2004  
KCC WICHITA

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION  
Please TYPE Form and File ONE Copy

September 2000  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 033-21392-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1987; if no API # was issued, indicate original spud or completion date 03/18/2004

Well Operator: Castell Exploration KCC License #: 31021 (Operator)

Address: 6908 N.W. 112th Street City: Oklahoma City

State: OK Zip Code: 73162 Contact Phone: (405) 722-5511

Lease: Gregg Well #: 1-19 Sec. 19 Twp. 33 S. R. 16  East  West

C - E/2 - W/2 - SE Spot Location / OCCO County: Comanche

1320 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1650 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  SM-IFD Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: 20" Set at: 45' Cemented with: 6 yards redi-mix Sacks

Surface Casing Size: 13 3/8" Set at: 315' Cemented with: Serv Lite 180sx / 60/40 Po Sacks

Production Casing Size: 4 1/2" Set at: 5137' Cemented with: AA-2 125sx Sacks

List (ALL) Perforations and Bridgeping Sets: 4 spf Miss 5058'-5078', 4 spf Miss 5043'-5052', 4 spf Miss 5032'-5037'  
5058-5078 5043-5052 5032-5037

Elevation: 1833' (  G.L. /  K.M. ) T.D.: 5140' FBTD: 5096' Anhydrite Depth: 860' base (State Permit Number)

Condition of Well  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): 200# hulls w/ 20-25 sx cement bottom, @ 860' 50 sx cement displaced w/ mud, @ 345' 100 sx cement, @ 40' sx cement, then top off.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filled?  Yes  No  
If not explain why? \_\_\_\_\_

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Rick Popp

Address: P.O. Box 187 Phone: (820) 786-5514

City / State: Holsington, KS 67544

Plugging Contractor: Sargent & Lillard Csg Pulling KCC License #: 32833 (Contractor)

Address: PO Box 1450 Woodward, OK 73802-1450 Phone: (580) 254-1881

Proposed Date and Hour of Plugging (if known): possible 30-45 days

Payment of the Plugging Fee (K.A.R. 88-2-11a) will be guaranteed by Operator or Agent

Date: 09/14/04 Authorized Operator (Agent) Randy Popp (Signature)

1/05

4/05

# KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor    Brian J. Moline, Chair    Robert E. Krehbiel, Commissioner    Michael C. Moffet, Commissioner

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Castelli Exploration, Inc.  
6908 N.W. 112th  
Oklahoma City, OK 73162

September 16, 2004

Re: GREGG #1-19  
API 15-033-21392-00-00  
E2W2SE 19-33S-16W, 1320 FSL 1650 FEL  
COMANCHE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.


**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888

Sincerely



David P. Williams  
Production Supervisor