

12-22

To: 6 031209 API NUMBER 15- 153-20,533-00-00
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW SW SE, SEC. 21, T 3 S, R 36 WAE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 8793 Lease Name Joe Cahoj Well # 1-D
Operator: James Dillie County Rawlins 155.42
Name & Address 4469 S. Winona Court
Denver, Colorado

Well Total Depth 4782 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well x Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Halliburton License Number

Address Oberlin, Ks.

Company to plug at: Hour: Day: 22 Month: Dec Year: 19 88

Plugging proposal received from James Dillie

(company name) James Dillie (phone)

were: 8 5/8" set at 345' w/275 sks. 5 1/2" set at 4781' w/275 sks. Perf at 4659' - 4745', 2 shots 50' below base of Dakota at 2500'. Order 400 sks

65/35 Poz 10% Gel 2% Dical, 500# Hulls. Halliburton Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part x None

Operations Completed: Hour: 11:10AM Day: 22 Month: Dec Year: 19 88

ACTUAL PLUGGING REPORT Squeeze 5 1/2" casing w/300 sks w/500# Hulls mixed in.

Last 200 sks cement to max psi 500#. Close in psi 150#. Squeeze 8 5/8" w/100 sks

cement to max psi 300#. Close in 150#.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
Back to id no. serve this plugging.

DATE 1-19-89
INV. NO. 23678

Gib S

Signed Carl Goodrow (TECHNICIAN)