

3-6

154  
R

6 031507

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 153-20,613-0000

NW SW, SEC. 20, T 3 S, R 36 W&E

1980 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8979

Lease Name Henry Cahoj Well # 3-D

Operator: Henry Cahoj

County Rawlins 155.02

Name & Address Box 18

Well Total Depth 4770 feet

McDonald, Ks. 67745

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 388

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number

Address Oberlin, Ks.

Company to plug at: Hour: AM Day: 6 Month: Mar Year: 19 91

Plugging proposal received from James Dillie

(company name) Henry Cahoj (phone)

were: 8 5/8 set at 388 w/275 sks. 5 1/2 set at 4764 w/815 sks cwc. PBSD 4700.

PF 4249 - 4735 Order 350 sks 65/35 poz 10% gel and 600 lbs. hulls.

Halliburton Cement Co. LaRue Water Trucks.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 10:20AM Day: 6 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Sq 5 1/2 casing w/325 sks cement blend w/

500 lbs. hulls mixed into max psi 1000 lbs. Close in psi 300 lbs.

Sq 8 5/8 to 500 lbs. psi w/6 bbl slurry (25 sks cement blend) w/100 lbs. hulls

mioxed in. Held 500 lbs. Plug complete.

RECEIVED STATE CORPORATION COMMISSION

Remarks: (If additional description is necessary, use BACK of this form.)

MAR 22 1991 3-22-91

INVOICED

APR 02 1991

DATE

WV. NO. 31262

Handwritten initials

Signed Carl Goodrow (TECHNICIAN)