

92

4-032386

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Number: 15-153-20,641 <sup>00-00</sup>

C E2 SW SW /4 SEC. 20, 03, 36 W  
660 feet from S section line  
4950 feet from E section line

Operator license# 8979

Lease: Cahoj Henry Well # 2-D

Operator: Cahoj H. Drilling

County: Rawlins

Address: P.O. Box 18  
McDonald, Kansas 67745

Well total depth 4750 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 342 feet

Aband. oil well X, Gas well     , Input well     , SWD     , D & A     

154.38

Plugging contractor: Poe Servicing Inc. License# 3152

Address: Oberlin, Kansas 67749

Company to plug at: Hour: P.M. Day: 2 Month: September Year: 1999

Plugging proposal received from: Ruby Poe

Company: Poe Servicing Inc. Phone:     

Were: Order 375 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[      ], Part[      ], None[ X ]

Completed: Hour: 5:30 A.M., Day: 2 Month: September, Year: 1999

Actual plugging report: 8 5/8" set at 342' w/350 sxs cwc. 5 1/2" set at 4750' w/N/A sxs. Squeezed 8 5/8" with 50 sxs cement blend to Max. P.S.I. 200#. Squeezed 5 1/2" with 325 sxs cement blend with 500# hulls to Max. P.S.I. 600#. S.I.P. 600#. Plug complete.


Remarks:     

Condition of casing(in hole): GOOD      BAD      Anhy.plug: YES X NO     

Bottom plug(in place): YES     , CALC     , NO      Dakota plug: YES X, NO     

Plugged through TUBING     , CASING     . Elevation:      GL

I did[      ] / did not[ X ] observe the plugging.

Carl Goodrow  
(agent) 

**INVOICED**  
DATE 9-24-99  
200060580

RECEIVED  
STATE CORPORATION COMMISSION  
Form CP-2/3  
**SEP 23 1999**  
9-23-99  
CONSERVATION DIVISION  
Wichita, Kansas