

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20400-00-01  
Spot: SWSW Sec/Twnshp/Rge: 36-3S-34W  
660 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: PALMER Well Number: 1-1336  
County: RAWLINS Total Vertical Depth: 4525 feet

Operator License No.: 9800  
Op Name: DOUBLE R OIL COMPANY INC  
Address: PO BOX 450 408 MAIN STREET  
ATWOOD, KS 67730

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 316  
Production: Size 4.5 feet: 4464  
Liner: Size feet:

*\$147.06*

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/11/2001 11:00 AM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 11 yards Redi-Mix - 6 sxs common cement with 3000# sand with 40 gallons water/yard.  
Add water as needed.

Plugging Proposal Received By: CARL GOODROW  
Date/Time Plugging Completed: 05/11/2001 12:00 PM

Witness Type: Plugging Operations Partially Witnessed  
KCC Agent: CARL GOODROW

**Actual Plugging Report:**

8 5/8" set at 316' w/200 sxs cwc. 4 1/2" set at 4464' w/380 sxs.  
PBTD 4500'. Prod. Perfs 4065' - 4073'.  
Fluid level at 4200'.  
Three shots recovered 1800' of 4 1/2" casing.  
Filled hole with 11 yards Redi-mix.  
Exempt area.

**INVOICED**

DATE 5-31-01.

INV. NO. 2001061866

**RECEIVED**  
KANSAS CORPORATION COMMISSION

MAY 31 2001  
05-31-2001  
CONSERVATION DIVISION

Remarks:

Plugged through: CSG

District: 04

Signed Carl Goodrow  
(TECHNICIAN)

*HD.*

MAY 17 2001

replacement card

DOUBLE R OIL COMPANY, INC.  
MCCOOK, NE 69001

36-03 -34W  
C SW SW

#1-1336 PALMER OWWO

site: 3-3/4 S & 2-1/4 W OF ATWOOD, KS  
contr: MURFIN DRILLING COMPANY

city: RAWLINS  
field: WC (BUSY BEAVER DISC)

API 15-153-20400-A

geol:	fr	spd	drig	card	last
	date	date	comp	issued	revised
	10/28/85	10/30/85	10/31/85	04/10/86	12/20/89


ELV: 3113 KB LOG

tops.....	depth/datum
ANH.....	2821 +292
HEEB.....	3980 -867
LANS.....	4020 -907
FT SC.....	4414 -1301
CONG.....	4616 -1503
MISS.....	4684 -1571
PBTD.....	4500 -1387
RTD OLD.....	4773 -1660

IP status:  
OIL, P 3 BOPD, TR WTR, LKC 4065-4073,  
CORRECTION: 12/20/89 - CORRECTED DST (5) - WAS  
5114-4142  
OLD INFO: OPERATOR WAS MOBLE C. HOOVER, 1 EVA  
PALMER, SPD 09/29/80 , 10/11/80 SET 8-5/8"  
316/200SX, D&A, MISS , 10/11/80 (CARD ISSUED  
10/23/80 )  
CONTR: ABERCROMBIE DRILLING  
GEOL: ORLIN R. PHELPS  
NO CORES  
DST (1) 3976-4033 (LANS), 7 30-45-60-45, REC 402' M &  
SW ISIP 1233# FSIP 1132# IFP 142# -183# FFP 214#  
-214#

COPYRIGHT 1989  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS

RECEIVED

(over)