

6030514

API NUMBER 15-153-20,614-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

CNWSE, SEC. 35, T. 3 S, R. 34 W1/4

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9800

Lease Name Brown Well #1-1035

Operator: Double R Oil Co.

County Rawlins 145.67

Name & Address Box 506

Well Total Depth 4482 feet

McCook, Nebraska

Conductor Pipe: Size _____ feet

69001

Surface Casing: Size 8 7/8 feet 260'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilg Co. License Number 6033

Address Wichita, Kansas

Company to plug at: Hour: AM Day: 5 Month: 7 Year: 19 85

Plugging proposal received from Keith VanPelt

(company name) Murfin Drilg Co. (phone) _____

were: 8 7/8 at @ 260' w/ 200af. With hole full of no less than 36

this mud. and no loss or gain of fluid spot cement plugs

with 2 1/2" pipe. Order 190af 60/40pg 6 7/8" 3 7/8" cc 8 7/8" w. P.

Halliburton Cement Co.

Order taken July 4th. @ 9:55PM with kindness and respect.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 5:30AM Day: 5 Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT Condition hole spot D.P. @ 2850' break

circ, Displace 25af cement mix, laydown D.P. to 2000' displace

100af cement mix + 1 sp flo cells laydown D.P. to 260' displace

40af cement mix. laydown D.P. Push W.P. to Kelly depth

and fill hole to base of collar with 10af cement mix, displace

15af cement mix in rat hole with joint of pipe. Plug complete

Remarks: Elev. 3097 Only 2810-53 Chokes 1 test.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.
DATE AUG 01 1985
Signed Carl Goodrow (TECHNICIAN) 4-26-85
INV. NO. 9261
7-5 AUG 06 1985
JUL 26 1985
07-26 1985
FORM CP-2/3 Rev. 01-84