

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-153-20166-00-01
Spot: NESWSWSW Sec/Twnshp/Rge: 25-3S-34W
440 feet from S Section Line, 440 feet from W Section Line
Lease/Unit Name: WEISHAPL Well Number: 1
County: RAWLINS Total Vertical Depth: 4195 feet

Operator License No.: 3602
Op Name: PHILPOTT OIL & GAS CO INC
Address: PO BOX 450 408 MAIN
ATWOOD, KS 67730

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 214
Production: Size 4.5 feet: 4082
Liner: Size feet:

8136.34

Well Type: OIL UIC Docket No: Date/Time to Plug: 05/03/2001 1:00 PM

Plug Co. License No.: 31664 Plug Co. Name: NORTHWEST WELL SERVICE, INC.

Proposal Rcvd. from: JIM Company: NORTHWEST WELL SERVICE, INC. Phone: (970) 522-4115

Proposed Plugging Method: Order 8 yards Redi-Mix - 6 sxs common cement with 3000# sand and 40 gallons water/yard.

Plugging Proposal Received By: CARL GOODROW

Witness Type: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 05/03/2001 2:00 PM

KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 214' w/175 sxs cwc. 4 1/2" set at 4082' w/140 sxs.
PBTD 4033'. Prod Perfs 3952' - 3955'.
Three shots recovered 1680' of 4 1/2" casing.
Filled hole with 8 yards Redi-Mix to surface (10 yards by yield).
This well is in exempt area.
Plug complete.

INVOICED

DATE 5-29-01

INV NO. 2001061838

RECEIVED
KANSAS CORPORATION COMMISSION

MAY 22 2001
05-22-2001
CONSERVATION DIVISION

Remarks:

Plugged through: CSG

District: 04

AD

Signed Carl Goodrow
(TECHNICIAN)

MAY 11 2001

PINNACLE PETROLEUM

518-17TH STREET, #540

DENVER, CO 80202

#1 WEISHAPL 'OWWO'

25-3-34W

440'FSL&

CONTR MURFIN DRILLING COMPANY

CTY


RAWLINS

440'FWL, SW/4

GEOL

FIELD

WC(4-3/4 N OF SAPP
CREEK ABD)



ELV 3043 KBSPD 1/27/83

CARD ISSUED

6/30/83

IP

P 10 BO & 11 BWPD

LKC 3952-3955

API 15-153-20,166-A

LOG	Tops	Depth/Datum	
ANH	2750+	293	<p>OLD INFO: OPERATOR WAS EMPIRE DRILLING COMPANY, #1 WEISHAPL, SPD 10/5/73, SET 8 5/8 " 214 / 175 SX, COMP. AS D&A / LANS 10/13/73, (CARD ISSUED 10/18/73), CONTR. MURFIN DRILLING COMPANY, GEOL: STEVE POWELL</p> <p>DST (1) 3940-3960 (OREAD, LANS) / 30-30-60-60, REC 280' HO & GCM, 20' SOCW, SIP 1182-1171#, FP 31-145#</p> <p>DST (2) 4067-4095 (ZN 5) / 30-30, REC 10' M, FSIP 1223#, FP 31-41#</p> <p>DST (3) 4095-4140 (ZN 6A) / 30-30-30-30, REC 25' THIN DRLG. MD, SIP 1296-1275#, FP 62-74#</p> <p>NEW INFO: FR 1/11/83, RE-ENTERED 1/27/83, WSH DWN, CO TO 4105, SET 4 1/2 " 4072/140SX; MICT - CO; PF (LKC) 3952-55, AC 4500G (3 TREATMENTS), SWB DWN, GSD, POP, P 10 BO & 11 BWPD, 6/1/83</p> <p>NOTE: 6/30/83 - ORIGINALLY FIRST REPORTED PRIVATE OIL INDUSTRIES AS OPERATOR; #1 'WD' WEISHAPL 'OWWO'</p>
B/ ANH	2792+	251	
TOP	3778-	735	
DEER CR	3863-	820	
U OREAD	3879-	836	
OREAD	3893-	850	
B/ OREAD	3917-	874	
LANS	3951-	908	
ZN 2A	3999-	956	
ZN 5	4045-	1002	
ZN 6A	4083-	1040	
ZN 7	4131-	1088	
ZN 9	4163-	1120	
LTD	4190-	1147	
RTD	4195-	1152	

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS