

6-8
API NUMBER 15- 023-20,271-00-00

To: 6 041046
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NW, SEC. 27, T 3 S, R42 W/E
feet from S section line
feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9860
Operator: Castle Resources
Name & Address: R. R. 1 Box 90
Hays, Ks. 67601

Lease Name Roile Well # 1
County Cheyenne 173.10
Well Total Depth 5326 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 302' w/200

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Halliburton Cement License Number
Address Oberlin, Ks.

Company to plug at: Hour: 10:00AM Day: 8 Month: June Year: 19 89

Plugging proposal received from Jerry Green
(company name) Castle Res. (phone)

were: 5 1/2" casing set at 4820' w/200 sks. Top perf at 4680'. Plug bottom
w/sand to 4475' and 5 sks cement. Ordered 350 sks 65/35 poz 10% gel
w/1/2# f.c. plus 8 sks hulls.

Plugging Proposal Received by Dennis L. Hamel
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30PM Day: 8 Month: June Year: 19 89

ACTUAL PLUGGING REPORT Show casing at 2500', recovered same; Ran tubing to 2498'.

Spotted 130 sks cement w/4 sks hulls mixed in cement, pulled tubing to 1450': Spotted
130 sks cement plus 4 sks hulls mixed in cement: pulled tubing to 400', circ cement to
surface w/80 sks cement: Pulled tubing, filled casing to surface w/10 sks cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 16 1989 6-19-89

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

INVOICED

DATE 6-21-89

INV. NO. 25094

Signed Dennis L. Hamel
(TECHNICIAN)

Dennis Hamel