

TO: L
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20083-00-00
Spot: CW2NE Sec/Twnshp/Rge: 7-3S-41W
3960 feet from S Section Line, 1980 feet from E Section Line
Lease/Unit Name: CULWELL Well Number: 1-7
County: CHEYENNE Total Vertical Depth: 2200 feet

Operator License No.: 31609
Op Name: PRIORITY OIL & GAS LLC
Address: 633 - 17TH STREET, STE 1520
DENVER, CO 80202

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 251 225 SX CMT
Production: Size 4.5 feet: 1580 125 SX CMT
Liner: Size feet:
\$71.50

Well Type: GAS UIC Docket No: Date/Time to Plug: 10/03/2001 9:00 AM
Plug Co. License No.: 31609 Plug Co. Name: PRIORITY OIL & GAS LLC
Proposal Rcvd. from: KEVIN Company: PRIORITY OIL & GAS LLC Phone: (303) 296-3435

Proposed Plugging Method: Order 100 sxs 60/40 pozmix - 10% gel - 300# hulls.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 10/03/2001 10:15 AM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 251' w/225 sxs cwc. 4 1/2" set at 1580' w/125 sxs.
Prod. Perfs at 1478' - 1480'; 1444' - 1454'.
PBTB 1548'.
Squeezed 4 1/2" with 65 sxs cement blend with 300# hulls mixed in to Max. P.S.I. 500#. S.I.P. 500#.
Squeezed 8 5/8" with 35 sxs cement blend to Max. P.S.I. 300#. Held.
Plug complete.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

JD

Signed

Carl Goodrow

(TECHNICIAN)

RECEIVED
10-18-2001
OCT 18 2001

KCC WICHITA

INVOICED


Form CP-2/3

DATE 10-18-01

INV. NO. 2002060825

OCT 05 2001

MURFIN DRILLING COMPANY
 617 UNION CENTER, #1-7 CULWELL 7-3-41W
 WICHITA, KS 67202 C W/2 NE
 CONTR MURFIN DRILLING CO. CTY CHEYENNE
 GEOL _____ FIELD CHERRY CREEK
 E 3594 KB CM 9/25/78 CARD ISSUED 3/6/80 IP SIGW NIOBRARA GAS AREA
 NIOB 1444-54



API 15-023-20,083

SMP	TOPS	DEPTH	DATUM
NIOB		1345	+2249
TD		2200	+1394

8-5/8" 251/225sx, 4 1/2" 1580/125sx
 NO DST'S
 MICT - CO, PF 1479-1480 & 8/1478-1480,
 SET PACKER @ 1431', SQZ'D W/150SX, PF
 80/1444-1454, FRAC W/600SX SD, 262 BW
 & 312,000 SCF NITROGEN, KO FLO 283
 MCFGPD, SIGW - POTENTIAL NOT AVAILABLE

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS