

8-10

4-031846

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-023-20,078-00-00

C SE SE /4 SEC. 06, 03 S, 41 W  
660 feet from S section line  
660 feet from E section line

Operator license# 5099 Lease Hilt well # 1

Operator: J-W Operating Company County Cheyenne

Address: P.O. Box 305 Well total depth 1640 feet <sup>53.30</sup>  
Wray, Colorado 80758 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 335 feet

Aband. oil well     , Gas well X, Input well     , SWD     , D & A     

Plugging contractor: Excell Drilling License# 2989

Address: Wray, Colorado

Company to plug at: Hour: A.M. Day: 9-10 Month: August Year: 93

Plugging proposal received from: Roland Leton-BLM and Ray Bivens J-W

Company: J-W Operating - Bureau of Land Management Phone:     

Were: Order 140 sxs. common cement. Cementers Inc. - Scottbluff, Nebraska.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All[      ], Part[ X ], None[      ]

Completed: Hour: P.M., Day: 9-10, Month: August, Year: 93

Actual plugging report: 8 5/8" set @ 335' w/310 sx. cwc. 4 1/2" set @ 1634' w/125 sxs. P.B.T.D. 1634'. Perfs. 1510' - 1534'. Loaded hole with KCL water. Set wireline CIBP @ 1460'. Shot off casing @ 953'. Pulled 4 1/2" washed down 953' to 1167'. Ran 2 3/8" tubing to 1167'. Hole fill up, circulated 40 sxs. cement to 885'. Pulled 2 3/8" up to 450' circulated 80 sxs. cement to 170'. Pulled 2 3/8" to 390' circulated cement to surface with 20 sxs. Used total of 140 sxs. common cement. Cut off and weld plate on 8 5/8". Back fill cellar. Plug complete.

Remarks:       
Condition of casing(in hole): GOOD X BAD      plug: YES X NO       
Bottom plug(in place): YES X, CALC      Dakota plug: YES X, NO       
Plugged through TUBING     , CASING      Elevation:      GL

I did not observe the plugging.

Carl Goodrow

(agent)

Form CP-2/3

RECEIVED  
STATE CORPORATION COMMISSION  
WICHITA, KANSAS  
AUG 31 1993  
CONSERVATION DIVISION

INVOICED

DATE 8-30-93

INV. NO. 38513