

8-3

4-041539

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-023-20,035-00-00

SE /4 SEC. 04, 03 S, 41 W
1720 feet from S section line
2240 feet from E section line

Operator license# 5099

Lease Robert Walters well # 3

Operator: J-W Operating Company

County Cheyenne

Address: P.O. Box 305
Wray, Colorado 80758

Well total depth 1663 feet ^{54.04}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 0 feet

Aband. oil well , Gas well X, Input well , SWD , D & A

Plugging contractor: Excell Drilling Company License#

Address: Wray, Colorado 80758

Company to plug at: Hour: 10:00A.M. Day 2 Month: August Year: 93

Plugging proposal received from:

Company: Phone:

Were: 4 1/2" casing set @ 1456'. O.H. @ 1456' - 1663'.
Ordered 100 sxs. common with 1/4# F.C.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 12:00P.M., Day: 3, Month: August, Year: 93

Actual plugging report: Plug bottom with sand to 1400' plus 4 sxs. cement on sand, cut-off 4 1/2" casing @ 894'. Spot 25 sxs. common cement. Pulled up to 335' spot 30 sxs. common cement. Pulled up to 50' circulate cement to surface with 20 sxs. cement. Pulled casing and filled to surface.

RECEIVED
STATE CORPORATION COMMISSION

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES NO
Bottom plug(in place): YES X, CALC , NO Dakota plug: YES NO
Plugged through TUBING , CASING X. Elevation: GL

I did [X] did not [] observe the plugging. Dennis L. Hamel

INVOICED
DATE 11-22-93
INV. NO. 39266

 (agent)