

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20032-00-00
Spot: SWNESWSE Sec/Twnshp/Rge: 4-3S-41W
880 feet from S Section Line, 1760 feet from E Section Line
Lease/Unit Name: ROBERT WALTERS Well Number: 2
County: CHEYENNE Total Vertical Depth: 4750 feet

Operator License No.: 31514
Op Name: THOROUGHbred ASSOCIATES L.L.C.
Address: 8100 E. 22ND ST. - BUILDING 600
WICHITA, KS 67226

Conductor Pipe: Size feet: 154.38
Surface Casing: Size 8.625 feet: 240 w/225 sxs cmt
Production: Size 4.5 feet: 4740 w/150 sxs cmt
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/13/2002 12:00 PM
Plug Co. License No.: 31465 Plug Co. Name: LYONS & LYONS, INC.
Proposal Rcvd. from: BUD RICE Company: LYONS & LYONS, INC. Phone: (918) 587-2497

Proposed Plugging Method: Order 350 sxs cement blend.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 02/13/2002 1:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 240' w/225 sxs cwc. 4 1/2" set at 4740' w/150 sxs.
Prod. Perf 4654' - 4664'.
Exempt area.
Squeezed 4 1/2" w/290 sxs cement blend slurry with 500# hulls mixed in to Max. P.S.I. 500#. S.I.P. 300#.
Squeezed 8 5/8" w/20 sxs to Max. P.S.I. 100#. Blew out casing. Plug complete.

RECEIVED
APR 19 2002
04-19-2002
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS CHERRY CREEK #2.
Plugged through: CSG

District: 04

Signed Carl Goodrow
(TECHNICIAN)

INVOICED

DATE 4-22-02
INV. NO. 2002061680

Form CP-2/3

APR 15 2002

SHAKESPEARE OIL CO.
BOX 669, SALEM, ILL.

#2 ROBERT WALTERS

4-3-41W
680' FSL &
1760' FEL, SE

CONTR MURFIN DRILG. CO.

CTY CHEYENNE

GEOL MR. HOLLENSBEE

FIELD CHERRY CREEK

E 3604 KB CM 3/20/77 CARD ISSUED 5/19/77 IP P 46 BOPD + WTR
LKC 4654-54

+	+	+
+	+	+
+	+	+

API 15-023-20,032

LOG	TOPS	DEPTH	DATUM
ADM		4058	- 454
HQW		4266	- 662
TOP		4312	- 708
DEER CR		4354	- 750
QREAD		4386	- 782
LKC		4458	- 854
LKC 'A'		4514	- 910
LKC 'C'		4568	- 964
LKC 'D'		4618	-1014
LKC 'E'		4650	-1046
RTD		4750	-1146
LTD		4750	-1146

8-5/8" 240/225sx, 4 1/2" 4740/150sx
DST (1) 4624-66/30-30-60-60, 120' CGO,
120' VSMCO, 120' HM&GCO, SIP 243-
243# FP 37-112# 131-187#
MICT - PF 40/4654-54, AC 500, SWB 5:
BOPH, N/W/3 HRS, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS