

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-023-20271-00-00

LEASE NAME Raile

WELL NUMBER 1

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 27 TWP. 3S RGE. 27 (E) or (W)

COUNTY Cheyenne

Date Well Completed 5/6/89

Plugging Commenced 6/8/89

Plugging Completed 6/8/89

LEASE OPERATOR Castle Resources

ADDRESS Rr1 - Box 90 Hays, Kansas

PHONE# (913) 625-5155 OPERATORS LICENSE NO. 9860

Character of Well Dry

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Hays- Dennis Hamel supervised

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation L-KC Depth to Top 4454 Bottom 4777 T.D. 4775

Show depth and thickness of all water, oil and gas formations.

RECEIVED
STATE CORPORATION COMMISSION
6-12-89
JUN 12 1989

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface	Water	302	0	8 5/8	302'	
Long String	Water	4820	0	5 1/2	4820	2500'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Sand to 4475 plus 5 sks. cement pull casing ran tubing to 2498. Spotted 130 sks. 65/35 cement w/400 # hulls pulled tbg to 1450 spotted 130 sks. cement 65/35 w/400# hulls, pulled tbg. to 400' circulate cement to surface w/80 sks. 65/35 pulled tubing filled casing to surface w/10 sks. cement

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Castle Resources License No. 9860


Address Rt 1 Box 90 Hays, Kansas

STATE OF Kansas COUNTY OF Ellis, ss.

Jerry Green (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jerry Green

(Address) _____



AND SWORN TO before me this 9th day of June, 19 89

Joseph C. Karlin
Notary Public

My Commission Expires: June 25, 1991