

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

18-147-20049-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 18 1968
CONSERVATION DIVISION
Wichita, Kansas
10-18-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Beacon Resources Corp.,

Complete Address: 312 Union Center Wichita, Kansas

Lease Name Zillinger Well No. 1

Location NW NE SW Sec. 4 Twp. 4 Rge. 18 (E) (W) XX

County Phillips Total Depth 3598'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated: _____

Plugging Contractor: L. J. Dreiling & Sons, Inc.

Address: Victoria, Kansas License No. _____

Operation Completed: Hour 12 M Day 15 Month 10 Year 1968

The Above well was plugged as follows:

RTD 3598' 8 5/8 csg set at 251' cwc Gmt. Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cmt.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Prof. Murray
Well Plugging Supervisor

DATE 10/18/68

INV. NO. 8654-u