

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

R

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -147-20,263-00-00 (of this well)

Operator's Full Name TERRA RESOURCES INC.

Complete Address P.O. BOX 839 OKLAHOMA CITY, OKLA.

Lease Name DEAN Well No. #1

Location C-SW-SW-SW-SE Sec 24 Twp. 4 Rge. 17 (E) (W) W

County PHILLIPS Total Depth 2700 FE.

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor EMPHASIS OIL OPERATIONS

Address BOX 506 - RUSSELL, MANS. 67665 License No.

Operation Completed: Hour 100 PM Day 2ND Month JAN Year 1980

The above well was plugged as follows:

8 5/8" 670 FE SP. CMC w/ 425 FE 60/40 POZMIX 2% GEL - 3% CH-CL. (ELEV 1858) ^{KB}

LOST CIRCULATION - SPOTTED - 150 FE COMMON CMT. + 100 FE 60/40 POZMIX

WITH 12% GILSONITE + 3% CH-CL. - 8% FLO. SEAL. - 2% GEL AT 1054 FE.

DRILLED THROUGH AND GOT CIRCULATION.

ORDERED 105 FE 50/50 POZMIX 6% GEL + 8 5/8 PLUG. (SPOTTED WITH DRILL STEM)

1ST PLUG @ 660 FE w/ 70 FE CMT + 2ND PLUG @ 290 FE w/ 20 FE CMT.

3RD PLUG. SOLID BRIDGE PLUG @ 40 FE w/ 10 FE CMT.

5 FE IN RAT HOLE CEMENTED BY ALLIED CEMENTING

I hereby certify that the above well was plugged as herein stated.

Signed: Manuel Schubert
Well Plugging Supervisor

1-7-80

INVOICED
DATE 1-8-80
V. NO. 1277-w