

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

15-147-20076-00-00

RECEIVED
STATE CORPORATION COMMISSION
AUG 28 1969
CONSERVATION DIVISION
Wichita, Kansas
8-28-69

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Don H. Peaker, Et al

Complete Address Pueblo, Colorado *BON DURANT Bldg. 81003*

Lease Name August Eikhoff Well No. 1

Location NW SE NW Sec. 7 Twp. 4 Rge. (E) (W) 18

County Phillips Total Depth 3430

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Red Tiger Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 6A Day 27 Month 8 Year 1969

The above well was plugged as follows:

RTD 3430' 8 5/8 csg set at 195' cwc 150 sk Cmt. Mat. 50-50 poz cmt W/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 180' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/28/69
INV. NO. 383-W

Signed: *Red J. Murray*
Well Plugging Supervisor