

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

15-147-00443-00-00

JUL 29 1975

CONSERVATION DIVISION  
Wichita, Kansas  
7-29-75

Operator's Full Name Phillips Oil Operating Co.

Complete Address Box 706, Enid, Oklahoma 73701

Lease Name Meyer Well No. 1

Location C SE SW Sec. 7 Twp. 4 Rge. (E) (W) 18

County Phillips Total Depth 3310'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 4 P Day 24 Month 7 Year 1975

The above well was plugged as follows:

Total Depth 3310' 8 5/8 csg set 160' cwc 120 sx.

5 1/2 csg set 3305' cw 85 sx cem. & perf. (3156')

Set 5 1/2 wood plug at 3000' -poured 20' sd -dumped 4 sk cem W/dump bailer. (3000-2950)

Cutoff & recovered 1005' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 15 sk gel & water W/300 lbs hulls -70' sx 50-50 poz

6% -15 sx gel & water -released 8 5/8 plug & 50 sx 50-50 poz 6%.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Messer  
Well Plugging Supervisor

INVOICED

DATE 7/30/75

INV. NO. 1686-W