

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

JUL 29 1975
07-29-75
CONSERVATION DIVISION
Wichita, Kansas

15-147-20091-00-01

Operator's Full Name Phillips Oil Operating Co.

Complete Address Box 706, Enid, Oklahoma 73701

Lease Name Meyer Well No. 2

Location C NW NW SW Sec. 7 Twp. 4 Rge. (E) (W) 18

County Phillips Total Depth 3435'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 2:30 P Day 24 Month 7 Year 1975

The above well was plugged as follows:

Total Depth 3435' 8 5/8 csg set 218' cwc 150 sk.

4 1/2 csg set 3434' cw 200 sx cem. with top perf. (3242')

Set 4 1/2 wood plug at 3000' -poured 20' sd -dumped 3 sk cem W/dump bailer. (3000-2950)

Cutoff & recovered 2257' of 4 1/2 csg.

Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk

50-50 poz 6% -10 sk gel & water -released plug & 50 sk 50-50 poz 6%.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Massey
Well Plugging Supervisor

INVOICED

DATE 7/30/75

INV. NO. 1687-w