

R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

STATE CORPORATION COMMISSION

NOV 12 1976

11-12-76

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -147-2019-0000 (of this well)

Operator's Full Name T. W. Jackson

Complete Address Route #4, Phillipsburg, Kansas 67661

Lease Name Jackson Well No. B-2

Location C NW SW Sec. 17 Twp. 4 Rge. (E) (W) 18

County Phillips Total Depth 3300'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 1 P Day 11 Month 11 Year 1976

The above well was plugged as follows:

Total Depth 3300' 8 5/8 csg set 215' cwc 125 sx.

4 1/2 csg set 3299' cw 200 sk cem. Pop perf. (3122')

4 1/2 csg squeezed thru "Dakato" section. Sand back to 3000' & 3 sx cem W/dump bailer.

Recovered 319' of 4 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 10 sk gel & water W/300 lbs

hulls & 100 sk "Comm" 4% gel. FPP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Messer  
Well Plugging Supervisor

INVOICED

DATE 11-15-76

INV. NO. 4153-W