

STATE OF KANSAS
STATE CORPORATION COMMISSION
Wichita State Office Building
130 South Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-177

API NUMBER 15-147-20601-0000

LEASE NAME Hanchett

WELL NUMBER 2

330 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 17 TWP. 4S RGE. 18W (E) or (W)

COUNTY Phillips

Date Well Completed 3/24/01

Plugging Commenced 3/24/01

Plugging Completed 3/24/01

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 West 12th Street Hays, KS 67601

PHONE #(785) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well D & A

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

The plugging proposal was approved on 3/24/01 (date)

by KCC District 4 (KCC District Agent's Name).

Is ACO-1 Filed? yes If not, is well log attached? already sent in

Producing Formation NA Depth to Top _____ Bottom _____ T.D. 3570'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 1/2"	219'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Ran in open hole with drill pipe and put 25 sx of 60/40 cement, 6% gel and 1/4# Flo seal at 1500'. Pulled to 896' and pumped 100 sx same cement. Pulled to 269' and pumped 40 sx same cement. Pulled to 40' and pumped 10 sx same cement. Put 15 sx in rathole and 10 sx in mousehole. (Murfin rig #16, drlg. contractor)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor R.P. Nixon Operations, Inc. License No. 5252

Address 207 West 12th Street Hays, KS 67601-3898

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 West 12th St. Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 26th day of July, 2001



My Commission Expires: 3/12/2005

[Signature]
Notary Public

OR