

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-023-20-016-00-00

LEASE NAME Schauer

WELL NUMBER #1-12

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

600' Ft. from ~~N~~Section Line

1980' Ft. from ~~W~~Section Line

SEC. 12 TWP. 3S RGE. 41 ~~XX~~or (W)

LEASE OPERATOR Mountain Petroleum Corporation

ADDRESS 7851 E. Maplewood, #130, Englewood, Co. 80111 COUNTY Cheyenne

PHONE# (303) 694-6038 OPERATORS LICENSE NO. 5713

Date Well Completed 5/17/76

Character of Well Gas

Plugging Commenced 9/6/85

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9/6/85

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6, Hays, Kansas

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Niobrara Depth to Top 1348' Bottom 1400 T.D. 1498'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Niobrara	Gas	surf.	260.70'	8 5/8"	7 jts	----
		260.70'	1498'	4 1/2"	38 jts	----
		surf.	1355'	1 1/2" tbg	45 jts	45 jts

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped 9 bbls, 60-40 poz, 6% gel, 3% cc down 4 1/2" csg., followed by 3 sx cottonseed hulls, then 60-40 poz, 6% gel, 3% cc until reaching pressure of 900 psig. Shut in 4 1/2". Hooked up to 4 1/2"-8 5/8" annulus, pumped 60-40 poz, 6% gel, 3% cc, plus 25 sx cottonseed hulls until reaching final pressure of 400 psig. Witnessed by Carl Goodrow.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Titan Cementers License No. _____

Address P.O. Box 169, Great Bend Kansas 67530

STATE OF Colorado COUNTY OF Denver, ss.

John P. Lockridge (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me God.

(Signature) John P. Lockridge

(Address) 1444 Wazee St., #218, Denver, Co.

SUBSCRIBED AND SWORN TO before me this 23 day of September, 19 85

Sarah J. [Signature]
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION

SEP 26 1985
 09-26-1985
 CONSERVATION DIVISION
 Wichita, Kansas

My Commission Expires: _____

My Commission Expires Feb. 17, 1986
 1444 Wazee St., Suite 218
 Denver, Colorado 80202