

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Wichita State Office Building  
130 South Market, Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-177

API NUMBER 15-147-20,159 -00-01

LEASE NAME Jackson B

WELL NUMBER 2

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 17 TWP. 4S RGE. 18W (E) or (W)

COUNTY Phillips

Date Well Completed 10/10/72

Plugging Commenced 5/8/97

Plugging Completed 5/8/97

LEASE OPERATOR R.P. Nixon Operations, Inc.

ADDRESS 207 West 12th Street Hays, KS 67601

PHONE #(913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well oil

(Oil, Gas, D&A, SWD. Input, Water Supply Well)

The plugging proposal was approved on 5/7/97 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 Filed? unknown If not, is well log attached? \_\_\_\_\_

Producing Formation L/KC Depth to Top 3081' Bottom 3300' T.D. 3300'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	215'	None
				4 1/2"	3296'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.  
Perf'd well @ 1430' and 825'. Ran tubing to 1500' and pumped 160 sx 60/40 Pozmix, 10% gel w/400# hulls. Cement circulated. Pulled tubing out of hole and tied onto 4 1/2" casing and pumped 50 sx same cement w/100# hulls. Maximum pressure 800#, shut-in pressure of 500#. Tied onto 4 1/2" annulus and pumped 5 sx same cement @ 500# pressure.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Jay-Lan Corporation License No. 5128

Address 207 West 12th Street Hays, KS 67601-3898

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: R.P. Nixon Operations, Inc.


STATE OF Kansas COUNTY OF Ellis, ss.

Dan A. Nixon (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 West 12th St. Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 4th day of June, 1997



My Commission Expires: 5-24-2001