



15-183-20004-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 20 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
9-20-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of L. J. Dreiling & Sons, Inc. has this date requested permission to plug the following described well:

Mr. Wilbur C. Bradley guarantees payment of the plugging fee.

Operator's full Name: George Ablah, c/o Wilbur C. Bradley

Complete Address: 1009 Union Center, Wichita, Kansas 67202

Lease Name: Lebanan Well No. # 1

Location: C NE NE Sec. 1 Twp. 4 Rge. 11 (E)(W) W

County: Smith Total Depth 4258 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Bill draper was instructed to plug the well as follows:

8 5/8" csg. 207' Cwc.

Circulated hole with heavy mud to 800', set plug, & displaced 70 sax

cement thru drill pipe. Mud to 215' & displaced 20 sax cement thru drill

pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement with

Allied Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

*Don L. ...*  
Conservation Division Agent