

State of Kansas



13-147-20076-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 28 1969
 CONSERVATION DIVISION
 Wichita, Kansas

8-28-69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Fickle of Red Tiger Drlg. has this date requested permission to plug the following described well:

Mr. Fickle guarantees payment of the plugging fee.

Operator's full Name: Don H. Peaker Et al

Complete Address: Pueblo, Colo.

Lease Name: August Eikhoff Well No. 1

Location: NW SE NW Sec. 7 Twp. 4 Rge. (E)(W) 18

County: Phillips Total Depth 3430' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Fickle was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace
70 sk cmt thru drill pipe. Heavy mud to 180' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
 Conservation Division Agent