

State of Kansas



15-147-30111-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 25 1966
3-25-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Fickle of Red Tiger Drilg. Co has this date requested permission to plug the following described well:

Mr. Fickle guarantees payment of the plugging fee.

Operator's full Name: Petroleum Management Inc.

Complete Address: 1515 Wichita Plaza, Wichita, Kans.

Lease Name: Zillingert Well No. 1

Location: 1660' 756 440' 9EL Sec. 5 Twp. 4 Rge. 18 (E)(W)

County Phillips Total Depth 2550 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fickle was instructed to plug the well as follows:

Run Pits. Circ. hole w/ clay mud. set wood Plug at 1540'
Displace w/ 20 SAG Cem. thru Drill Pipe. Fill Hole w/ clay Mud
to 180' set wood Plug displace w/ 20 sag Cem. thru Drill Pipe
Fill Hole w/ clay mud to 40' - Build solid Bridge of Wood
Plug, 1/2 SAG hulls & 10 SAG Cem. to base of Cellar. 2 SAG Rathole

Very truly yours,

Leo Massey
Conservation Division Agent