

15-147-19084-00-01

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: ~~15-147-00941-00-00~~
Spot: CNWNWNW Sec/Twnshp/Rge: 7-4S-18W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease/Unit Name: KRAUS - A Well Number: 4
County: PHILLIPS Total Vertical Depth: 3662 feet

Operator License No.: 31668
Op Name: H & H INVESTMENTS
Address: PO BOX 1433
HAYS, KS 67601

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 330
Production: Size 5.5 feet: 3434
Liner: Size feet:

\$119.02

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/02/2001 1:00 PM
Plug Co. License No.: 31668 Plug Co. Name: H & H INVESTMENTS
Proposal Rcvd. from: RON Company: H & H INVESTMENTS Phone: (785) 362-5663

Proposed Plugging Method: Order 10 yards Redi-Mix - 6 sxs common cement - 3000# sand - 40 gal water per yard.
Workover rig on hole - bad casing. Sanded in - tried to clean out - could not. P&A.
Swabbed hole dry.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 07/02/2001 2:00 PM KCC Agent: CARL GOODROW

Actual Plugging Report:

8 5/8" set at 330' xwc. 5 1/2" set at 3434'.
Prod. Perfs 3324' - 3329'. PBTD 3360'. Bad casing - sanded in - swabbed hole.
Filled 5 1/2" with 8 yards Redi-Mix.
Filled 8 5/8" annulus with 2 yards Redi-Mix.
Plug complete.

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 20 2001
CONSERVATION DIVISION

Remarks:

Plugged through: CSG

INVOICED

DATE 7-23-01
INV. NO. 2002060103

District: 04

ND

Signed Carl Goodrow

(TECHNICIAN)

JUL 06 2001

SOHIO PETROLEUM

#4 KRAUS 'A'

7-4-18W
NW NW NW

Contr. BILL HAY

PHILLIPS County

E- 2013 R² Comm.

Comp. 7-2-54

IP 327 BOPD

PERM PMPG

Tops	Depth	Datum
KC	3225	-1212
B/KC	3453	-1440
ARB	3604	-1591
T.D	3662	-1649

Casing

8" 330

5" 3434

DST 3254-72/1 HR; 135' o & GCM, 190'

SLT WTR: DST 3305-37/1 HR, 115' OIL


189' V H GCM, BHP 1140#; PERF.

3384-88: ACID 1000: 40 BFPH, 75% WTR;

PB 3360: PERF 3324-29: WTR: SQZ:

PERF 3324-29: ACID 1000:

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS



3201027