

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-05806-00-00  
Spot: NENWSW Sec/Twnshp/Rge: 22-11S-17W  
2310 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: BEMIS Well #: 5  
County: ELLIS Total Vertical Depth: 3422 feet

Operator License No.: 3273  
Op Name: LOEB, HERMAN L.  
Address: PO BOX 524  
LAWRENCEVILLE, IL 62439

PROD Size: 5.5 feet: 3417  
SURF Size: 8.625 feet: 1128

#111 <sup>22</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/13/2004 11:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/13/2004 4:30 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perfs:

Sanded off casing to 3340' and topped with 5 sxs cement using a dump bailer.  
Perforated casing at 600' - 1130' - 1750'.  
TIH with tubing to 1800' - mixed and circulated cement with 160 sxs cement and 550# hulls.  
POOH.  
Perforated caing at 200'.  
Swaged onto 5 1/2" and circulated cement up 8 5/8" with 50 sxs.

RECEIVED  
SEP 17 2004  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer  
(TECHNICIAN)

INVOICED

DATE 9-17-04

INV. NO. 2005060539

Form CP-2/3

SEP 15 2004

BRITISH AMERICAN OIL #5 BEMIS 22-11-17W  
 PROD CO NE NW SW

Contr. \_\_\_\_\_ ELLIS County

E 1921 Comm 3-9-37 Comp 4-8-37 IP 2471 BOPD

Tops	Depth	Datum	Casing
ANH	1126		10" 1128
TOP	2880		6" 3417
LANS	3180		FU 3100' OIL
SIMP	3390		
ARB	3417		
TD	3422		


INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

1128  
 3417  
 3100' OIL