

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22307-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 5-14S-15W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: DORTLAND C Well #: 2
County: RUSSELL Total Vertical Depth: 3342 feet

Operator License No.: 6772

PROD Size: 5.5 feet: 3341 150 SX CMT

Op Name: WEIGEL, V. FRANCIS - FAMILY PARTN

SURF Size: 8.625 feet: 948 400 SX CMT

Address: PO BOX 219
GORHAM, KS 67640

108⁶²

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/07/2004 1:30 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: JOE MAES

Company: QUALITY WELL SERVICE, INC.

Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 180 sxs 60/40 pozmix - 10% gel - 500# hulls.
Cut casing loose at 2350'.

Plugging Proposal Received By: JAY PFEIFER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/07/2004 3:00 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3000' and topped with 5 sxs using a dump bailer.
Cut casing loose at 2350'.
Pulled up to 1400' - mixed and pumped 90 sxs cement with 400# hulls.
Pulled up to 950' - spotted 40 sxs cement with 100# hulls.
Pulled up to 300' and circulated with 50 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3366	3372		
3239	3239		
3229	3229		
3209	3212		
3190	3193		
3050	3056		

RECEIVED
SEP 17 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE 9-17-04

INV. NO. 2005060542

Form CP-2/3

SEP 13 2004

REPLACEMENT CARD

V. FRANCIS WEIGEL
 BOX 244
 GORHAM, KS. 67640


5-14-15W
 NW NW NW

#2 "C" DORTLAND

CONTR SHIELDS DRILLING CO. CTY RUSSELL

GEOLOGICAL FRANCIS WHISLER FIELD GORHAM

ELV 1893 KB SPD 2/10/84 CARD ISSUED 8/30/84 # P 15 BOPD & WTR
1888 GL LKC 3075-82



LOG	Tops	Depth/Datum
*ANH	940+ 953
*B/ ANH	978+ 915
TOP	2777- 884
HEEB	2999-1106
TOR	3020-1127
LANS	3049-1156
BKC	3290-1397
GRAN WSH	3298-1405
LTD	3314-1421
RTD	3342-1449

API 15-167-22,307

8 5/8 " 948 / 400SX, 5 1/2 " 3341 / 150SX

NO DST'S

MICT - CO, PF (LANS B) 3075-82, ACIDIZED (AMT NA), SWB LD,
 SO, POP, P 15 BOPD & WTR 3/15/84

INFO RELEASED: 10/4/84 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

MADE IN U.S.A.
 10/4/84