

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22979-00-00
Spot: NWSENE SW Sec/Twnshp/Rge: 27-7S-18W
1955 feet from S Section Line, 3275 feet from E Section Line
Lease Name: KOLLMAN Well #: 1
County: ROOKS Total Vertical Depth: 3379 feet

Operator License No.: 31828
Op Name: STEWART, STEPHEN R. DBA AARON O
Address: 2511 E 21ST
HAYS, KS 67601

CIBP Size: feet: 3260
COND Size: 13.38 feet: 55 w/35 sxs cmt
PROD Size: 5.5 feet: 3358 w/100 sxs cmt
SURF Size: 8.625 feet: 1271 w/425 sxs cmt

\$109⁸²

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2004 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 230 sxs 60/40 pozmix - 10% gel - 500# hulls.
Cut casing loose at 2460'.

Plugging Proposal Received By: JAY PFEIFER WitnessType: NONE
Date/Time Plugging Completed: 09/10/2004 2:00 PM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 2940' and topped with 5 sxs cement using a dump bailer.
Cut casing loose at 2460'.
Pulled up to 1800' - mixed and pumped 100 sxs cement with 300# hulls.
Pulled up to 1250' - spotted 40 sxs cement with 100# hulls.
Pulled up to 650' - spotted 30 sxs cement with 100# hulls.
Pulled up to 200' and circulated cement with 30 sxs.

Perfs:

Top	Bot	Thru	Comments
2992	2996		
2942	2945		
2918	2924		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

HP
Jay Pfeifer

(TECHNICIAN)

INVOICED

DATE 9-17-04
REF. NO. 2005060541

SEP 13 2004

HESS OIL COMPANY
MCPHERSON, KS 67460

27-07 -18W
1955'FSL & 3275'FEL, SEC

#1 KOLLMAN

site: 3/4 S & 2 W OF STOCKTON, KS
contr: MALLARD JV, INC
geol: JAMES C. HESS

city: ROOKS API 15-163-22979

field: W 1/4 NW 1/4 (OF JOELF)

fr date 01/05/88 spd date 01/25/88 drig comp 02/02/88 card issued 06/15/88 last revised 06/15/88

ELV: 1820 KB SMP
tops.....depth/datum
ANH.....1266 +554
B/ANH.....1300 +520
TOP.....2761 -941
HEEB.....2971 -1151
TOR.....2994 -1174
LANS.....3012 -1192
BKC.....3250 -1430
ARB.....3303 -1483
RTD.....3379 -1559
LOGGED

IP status:
OIL, P 10 BO & 22 BWPD, LKC 3011-3048 OA,
NOTE: CORRECTION: 2/17/88 - ORIGINALLY FIRST
REPORTED IN C NE SW
CSG: 13-3/8" COND AT 55 / 35 SX, 8-5/8" 1271 / 425
SX, 5-1/2" 3358 / 100 SX
NO CORES
DST (1) 3010-3080 (LANS), / 30-30-60-45, REC 265'
OCM (18% OIL, 82% M) ISIP 1168# FSIP 1158# IFP
109# -109# FFP 131# -152# IHP 1165# FHP 1614#
DST (2) 3290-3315 (ARB), / 60-30-60-30, REC 5' FREE
OIL, 80' OCM (15% OIL, 85% M) ISIP 264# FSIP 198#
IFP 110# -121# FFP 121# -132# IHP 1733# FHP 1722#

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

(over)

HESS OIL COMPANY
MCPHERSON, KS 67460

27-07 -18W
1955'FSL & 3275'FEL, SEC

#1 KOLLMAN

MICT CO, PF (ARB) 3303-3315, W 1/2 SW 1/4 AC 500 GAL (15%), SWB LD, RE AC 1000 GAL (28%), NON-COMMERCIAL, SET BP AT 3260, PF (LKC) 3011-3012, 3047-3048, W 1/2 SW 1/4 AC 750 GAL (15%), SWB LD, SO, RE-AC 3000 GAL (15%), SO, SET 2-7/8, TBG AT 3240, POP, P 10 BO & 22 BWPD, 5/16/88