

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22780-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 17-12S-15W
1650 feet from S Section Line, 4950 feet from E Section Line
Lease Name: HOLLAND Well #: 10
County: RUSSELL Total Vertical Depth: 3540 feet

Operator License No.: 5184
Op Name: SHIELDS OIL PRODUCERS INC
Address: 326 MAIN
RUSSELL, KS 67665

PROD Size: 5.5 feet: 3416 200 SX CMT
SURF Size: 8.625 feet: 945 375 SX CMT

Well Type: SWD UIC Docket No: D25147.0 Date/Time to Plug: 09/16/2004 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 500# hulls.

Plugging Proposal Received By: JAY PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2004 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

Sanded back casing to 3350' and topped with 5 sxs cement using a dump bailer.
Cut casing loose at 1820'.
Pulled up to 1575' - mixed and pumped 110 sxs cement with 300# hulls.
Pulled up to 950' - spotted 40 sxs cement with 100# hulls.
Pulled up to 450' and circulated cement with 60 sxs cement with 100# hulls.

Perfs:

Top	Bot	Thru	Comments
3416	3540		

RECEIVED
SEP 20 2004
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Jay Pfeifer
(TECHNICIAN)

INVOICED

DATE

9-20-04

INV. NO.

2005060545

SEP 17 2004

SHIELDS OIL PRODUCERS, INC
RUSSELL, KS 67665

17-12 -15W
SW NW SW

#10 HOLLAND

site: 8-1/4 N OF GORHAM, KS city: RUSSELL API 15-167-22780
contr: SHIELDS DRILLING COMPANY, INC field: FAIRPORT
geol: FRANCIS WHISLER
fr spd drlg card last
date 07/07/87 date 07/10/87 comp 07/16/87 issued 08/26/87 revised 08/26/87

ELV: 1899 KB SMP
topsdepth/datum
ANH.....935 +964
B/ANH.....977 +922
TOP.....2749 -850
HEEB.....2970 -1071
TOR.....2994 -1095
LANS.....3023 -1124
BKC.....3275 -1376
GORHAM SD.....3311 -1412
CONG.....3318 -1419
ARB.....3360 -1461
GRAN WSH.....3518 -1619
RTD.....3540 -1641

IP status:
SWDW, ARB-GRAN WSH OH 3416-3540,
CSG: 8-5/8" 945 / 375 SX, 5-1/2" 3416 / 200 SX
NO CORES
DST (1) 3308-3318 (GORHAM SD, CONG), / 30-45-10-0,
REC 20' M, W / FEW SPTS OIL, FP NA ISIP 916#
MICT - CO, (ARB-GRAN WSH OH), AC 3000 GAL, SET
2-1/2" TBG AT 3420, SWDW - INJECTION RATE
SATISFACTORY

COPYRIGHT 1987
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS