

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-60011-00-01  
Spot: NESWSW Sec/Twnshp/Rge: 26-14S-16W  
990 feet from S Section Line, 4290 feet from E Section Line  
Lease Name: HEYL Well #: 2 SWD  
County: ELLIS Total Vertical Depth: 3650 feet

Operator License No.: 31313  
Op Name: J.R. OIL CO. (ROME, JEROME DBA)  
Address: 961 CATHARINE ROAD  
HAYS, KS 67601

L1 Size: 3 feet: 3649 w/50 sxs cmt  
PROD Size: 5.5 feet: 3361 w/200 sxs cmt  
SURF Size: 8.625 feet: 705 w/400 sxs cmt

63  
\$118

Well Type: SWD UIC Docket No: D17535.0 Date/Time to Plug: 09/15/2004 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: JIM SCHOENBERGER Company: J.R. OIL COMPANY Phone: (785) 483-8027

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 10% gel - 600# hulls.  
Ordered 100 sxs 60/40 pozmix - 10% gel with 3% ccl - 400# hulls.  
Fluid level below 600'.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/16/2004 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Dug out backside and cut a hole to weld 2" nipple - backside was full of cement. Visual check. Allied tied to 5 1/2" casing with a swedge - pumped 250 sxs with 600# hulls mixed in - well went on vaccum.  
Left set one hour and pumped 50 more sxs 60/40 pozmix.  
Left set two hours and pumped 50 sxs 60/40 pozmix.  
Left set two hours and pumped 100 sxs with 3% ccl with 400# hulls.  
Topped well with three yards cement slurry.

Perfs:


Top	Bot	Thru	Comments
3599	3649		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

  
(TECHNICIAN)

INVOICED

DATE 9-20-04

INV. NO. 2005060544

Form CP-2/3

SEP 17 2004

CORRECTED CARD

DREILING OIL CO., INC.

#2 HEYL "SWDW"

26-14-16W  
NE SW SW

VICTORIA, KS.  
CONTR. CO. TOOLS

CTY. ELLIS

GEOL.


FIELD DREILING SE POOL

E 1832 KB

6/25/74 CARD ISSUED 7/11/74

IP SWDW

ARB 3359-3636



LOG	TOPS	DEPTH	DATUM
ANJ		925-965	
HEEB		3028	-1196
TUR		3045	-1213
DOUG		3058	-1226
LANS		3075	-1243
BKC		3310	-1478
ARB		3363	-1531
GR WASH		3636	-1804
RTD		3649	-1817
DD TD		3650	-1818

OLD INFO: OPERATOR WAS SUN OIL, SPD  
 6/17/53, 8" 705, 5" 3361, COMPLETED AS  
 P 176 BOPD/PP  
 DST (1) 3073-3112/2', 440' GAS, 40' HO &  
 GCM, 60' O&MC SLT WTR, BHP 44#,  
 DST (2) 3322-49/2', 290' VHOCM, 200' G,  
 BHP 675#  
 CO 330, PF 64/3072-88, SWB 180 & 1GW,  
 PH 4 1/2", ACID 2000, SWB 125B0 & 111  
 SLT WTR/3HRS, SWB 327B0 & 64BW/12HRS

NEW INFO: SET 5 1/2" 3359/50SX, DD 3650',  
 CO 3650', RAN 3" PERFORATED LINER FROM  
 3000 TO 3650/50SX

CORRECTED CARD: 11/7/74  
 CORRECTED LOG TOPS

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS

11-10-74