

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-147-30083-00-00
Spot: N2SENE Sec/Twnshp/Rge: 29-4S-18W
3630 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: QUANZ A Well Number: 1
County: PHILLIPS Total Vertical Depth: 3315 feet

Operator License No.: 31569 Conductor Pipe: Size feet: 107.74
Op Name: BACH, JASON DBA BACH OIL PRODUCT Surface Casing: Size 8.625 feet: 198 140 sx
Address: RR 1, BOX 28 Production: Size 4.5 feet: 3333 200 sx
PHILLIPSBURG, KS 67661 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/08/2002 1:00 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: GARY L. REED Company: BACH OIL PRODUCTION Phone: (316) 733-4798

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Casing squeezed 880' - 1990' with 350 sxs cement.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/08/2002 2:30 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

R.I.H. with tubing to 2000'.
Spotted 120 sxs cement with 400# hulls to circulate at surface.
POOH with tubing - squeezed casing with additional 80 sxs cement.
Max. P.S.I. 1000#. S.I.P. 500#.
R.U. Cementers to 8 5/8" S.P.
Squeezed 25 sxs cement with 100# hulls.
Max. P.S.I. 500#. S.I.P. 300#.

11-25-02

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

1102

Signed

Dennis L. Hamel
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 12-2-02

INV. NO. 2003060884

12-78 * Map No. _____ REPL. COMP.
 OPER PETROLEUM MGMT. INC. - WICHITA, KS. S-T-R 29-4S-18W
SPOT N/2 SE NE
 WELL #1 QUANZ "A" CO PHILLIPS (KS)
 CONTR RED TIGER ELEV 1893 KB
 FIELD STONEMAN FIELD (LAN) (KB LOG)
 I.P. P 40 BOPD-NW, GR 37.7, LAN 3093-3268

SPUD 10-29-65 8" 198 W/140 SX. JOE RAKASKAS - GEOL
 DST #1 (LAN) 3140-3175, OP 30", SI/45", OP 30", SI/45",
 160' GIP, R 140' MCGO + 180' OGCM + 60' M, ISIP 1087#/
 30", FP'S 109-174#, FSIP 1068#/30"
 RTD 3315, LOG, 4 1/2" 3333 W/200 SX.
 PF 3093-3268 (LAN), TREATMENT NA, STATE POT: P 40
 BOPD-NW, GR 37.7, LAN 3093-3268 - COMP (12-7-65)
 REPLACEMENT COMPLETION (3-31-66)
 REPLACED WITH CORRECTED INFO AND TOPS

(KB LOG)
 ANH 1407 + 486
 TOP 2830 - 937
 HB 3032 -1139
 TOR 3036 -1143
 LAN 3071 -1178
 BKC 3295 -1402
 RTD 3315 -1422

Data Inc

12-78 * Map No. _____
 OPER PETROLEUM MANAGEMENT, INC. S-T-R 29-4S-18W
 Wichita, Kansas SPOT C N/2 SE NE
 WELL #1 QUANZ "A" CO PHILLIPS, KS
 CONTR Red Tiger Drilling ELEV 1893 KB
 FIELD Stoneman Field (Lans) (KB Spl's:)
 I.P. Temp Comp - P 40 BOPD-NW, Gr 37.7°, Lans
 3093-3268

(KB Spl's:)
 Anh 1430 + 463
 Hb 3051 -1158
 Lans 3090 -1197
 RTD 3335 -1442

(DST's not Released), RTD 3335, Log, 4 1/2" @3333' w/200 Sx.
 State Pot: P 40 BOPD-NW, Gr 37.7 deg, Lans 3093-3268
 Temp Comp - Data, Inc. Will report info when released
 COMPLETED on 12-7-65

Data Inc