

12-8

4-020038

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-147-20,013 ⁰⁰⁻⁰⁰
C NW SW /4 SEC. 19, 04 S, 17 W
1980 feet from S section line
4620 feet from E section line

Operator license# 7122
Operator: Keesee Oil Company
Address: 785 Third Street
Phillipsburg, Kansas 67661

Lease: Selbe Well # 1
County: Phillips
Well total depth 3307 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 223 feet

107.48

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling, Inc. License# 6050

Address: P.O box 347, Chase, Kansas 67524

Company to plug at: Hour: Day: 8 Month: December Year: 1993

Plugging proposal received from: Lowell Keesee

Company: Keesee Oil Company Phone: 913/543-5014

Were: 8% surface casing set @ 223'; 4 1/2" production casing @ 3306'
w/625 sx cmt; Elevation: 1792' KB/ 1785' GL; T.D.: 3307'; P.B.T.D.:
3079'; Heebner formation depth: 2984'; Perforations @ 3070-72', 3064-
3068', 3027-33';

Ordered 137 sx cmt 60/40 pozmix w/10% gel and 300# hulls.

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00, Day: 8, Month: December, Year: 1993

Actual plugging report: Pumped < 1 bbl cmt into 8% surface casing and
pressured to 700#, discontinued pumping - press. held @ 700#, discon-
nected from 8%". Pumped 25 sx cmt w/100# hulls into the 4 1/2" production
casing. Pumped 6 sx gel w/100# hulls into 4 1/2" casing. Pumped 111 sx
cmt (in 37 bbls.) into 4 1/2" w/100# hulls. Static pumping pressure: 300#,
Maximum pumping pressure: 1000#, End pressure after pumping: 400#.
Completion time: 12:00 (noon)

Remarks: Allied Cementing performed the cementing.

Condition of casing(in hole): GOOD X BAD Any plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: 1785 GL

RECEIVED

DEC 10 1993

I did not observe the plugging.

[Signature]
(agent)

CONSERVATION DIVISION
Wichita, Kansas

Form CP-2/3

12-10-93

INVOICED

DATE DEC 14 1993

INV. NO. 39513