

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-023-20012-00-01 **X02**  
Spot: CNWNW Sec/Twnshp/Rge: 10-3S-41W  
4620 feet from S Section Line, 4620 feet from E Section Line  
Lease/Unit Name: MARVIN ORTH Well Number: 1  
County: CHEYENNE Total Vertical Depth: 4770 feet

Operator License No.: 31514  
Op Name: THOROUGHbred ASSOCIATES L.L.C.  
Address: 8100 E. 22ND ST. - BUILDING 600  
WICHITA, KS 67226

Conductor Pipe: Size feet: \$155.03  
Surface Casing: Size 8.625 feet: 280 w/225 sxs cmt  
Production: Size 4.5 feet: 4752 w/150 sxs cmt  
Liner: Size feet:

Well Type: EOR UIC Docket No: E18584.4 Date/Time to Plug: 02/13/2002 9:00 AM  
Plug Co. License No.: 31465 Plug Co. Name: LYONS & LYONS, INC.  
Proposal Rcvd. from: BUD RICE Company: LYONS & LYONS, INC. Phone: (918) 587-2497

Proposed Plugging Method: Order 350 sxs cement blend.

Plugging Proposal Received By: CARL GOODROW Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 02/13/2002 10:00 AM KCC Agent: CARL GOODROW

**Actual Plugging Report:**

8 5/8" set at 280' w/225 sxs cwc. 4 1/2" set at 4752' w/150 sxs.  
Exempt area.  
Tubing fish in hole at 900'. The well was still taking.  
Prod. Perf. 4662' - 4666'.  
Squeezed 4 1/2" and circulated cement out 4 1/2" x 8 5/8" annulus.  
Shut in 8 5/8" and squeezed with 4 1/2" with 250 sxs cement slurry,  
with 500# hulls mixed in to Max. P.S.I. 500#. S.I.P. 100#.  
Plug complete.

RECEIVED

APR 19 2002  
04-19-2002  
KCC WICHITA

Remarks: LEASE ORIGINALLY KNOWN AS CHERRY CREEK #1.

Plugged through: CSG

District: 04

Signed

Carl Goodrow

(TECHNICIAN)

INVOICED

DATE 4-22-02

INV. NO. 2002061680

Form CP-2/3

APR 15 2002

SHAKESPEARE OIL CO., INC.

#1 MARVIN ORTH

10-3-41W  
C NW NW

P.O. BOX 669, SALEM, ILL.  
CONTR MURFIN DRIG. CO.

CTY CHEYENNE

GEOLOGICAL DAVID BRIERLY

FIELD WC (UNNAMED DISC)

E 3600 KB CM 11/4/75 CARD ISSUED 3/11/76

IP P 204 BOPD + 6 BWPD  
LKC 4662-66

o		
+	+	+
+	+	+
+	+	+

API 15-023-20,012

LOG TOPS	DEPTH	DATUM
NIQB	1444	+2165
ADM	4072	- 463
HOW	4270	- 661
TOP	4314	- 705
DEER CR	4358	- 749
OREAD	4390	- 781
HEEB	4418	- 809
LKC	4460	- 851
RUES ZN	4518	- 899
ORTH ZN	4662	-1053
LTD & RTD	4770	-1161

8 5/8" 280/225SX, 4 1/2" 4752/150SX  
 DST (1) 4434-70/60", 5'M, SIP 46#,  
 FP NA  
 DST (2) 4616-4660/30-30-30-60, 545'FL,  
 245'MGO, 60'CO, 60'HOCM, 60'OCM,  
 125'SOCM, N/W, SIP 1540-1540#, FP  
 115-242#, 227-300#  
 MICT - PF 4662-66, SWB 1 1/2 BOPH, NAT  
 SD/16HRS, FU 1500' OIL + 500' GAS, A  
 500, SWB LD & SWB 76 BO/3HRS, SWB 29  
 BOPH/3HRS, POP, P 140 BO N/W, 16HRS,  
 P 212 BOPD + 4% W, P 206 BOPD + 3% W

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS

15-023-20012-00-01  
4-17-02

**Olivia:**

**Please send invoice to:**

**# 31465**

**Lyons & Lyons, Inc.**

**1519 S. Baltimore**

**Tulsa, OK 74119**

**Thanks!**

**Sheila**

**District #4**

**Hays, Kansas 67601**