

5-8

4-041899

API Number: 15-147-20,159 -00-01

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

C NW SW _____ /4 SEC. 17 , 04 S, 18 W
1980 feet from S section line
4620 feet from E section line

Operator license# 5252

Lease: Jackson "B" Well # 2

Operator: R.P. Nixon Operations, Inc.

County: Phillips 107.25

Address: 207 W. 12th Street
Hays, Kansas 67601-3898

Well total depth 3300 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 215 feet
w/ 140 sxs.cmt.

Aband. oil well X, Gas well _____, Input well _____, SWD _____, D & A _____

Plugging contractor: Allied Cementing License# _____

Address: Russell, Kansas 67665

Company to plug at: Hour: 10:00A.M. Day: 8 Month: May Year 1997

Plugging proposal received from: Paul Nixon

Company: R.P. Nixon Operations, Inc. Phone: _____

Were: 4 1/2" casing set at 3296' w/125 sxs cement. Perfs at 3144' - 3186'. Anhy. at 1430'.
Dakota at 825'- W.L.M. at 3160'. Casing squeeze at 1007'-1039' w/70 sxs.
Ordered 275 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls.

RECEIVED
KANSAS CORP COM
JUN 11 A 1:13

Plugging Proposal Received by: Herb Deines
Plugging operations attended by agent? All[], Part[X], None[]

6-4-97

Completed: Hour: 3:00 P.M., Day: 8, Month: May, Year: 1997

Actual plugging report: R.I.H. with 1600' and spotted 160 sxs cement with 400# hulls -
cement at surface. P.O.O.H. with tubing - squeezed casing with 50 sxs cement - 100# hulls.
Max. P.S.I. 800#. S.I.P. 500#.
R.I.G. up to 8 5/8" S.P. Squeezed 5 sxs cement with Max. P.S.I. 700#. S.I.P. 500#.

Remarks: _____
Condition of casing(in hole): GOOD _____ BAD X Anhy.plug: YES X NO _____
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING X, CASING _____ Elevation: _____ G.L. _____

I did[X] / did not[] observe the plugging.

Dennis L. Hamel
(agent)

INVOICED

DATE JUN 09 1997

NV. NO. 48295