

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20151-00-00
Spot: NWNW Sec/Twnshp/Rge: 34-25S-21W
4620 feet from S Section Line, 4620 feet from E Section Line
Lease Name: HEMMEKE Well #: 34-4
County: FORD Total Vertical Depth: 4815 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 130 S. MARKET
WICHITA, KS 67202

PROD Size: 4.5 feet: 4814 WITH 250 SX CMT
SURF Size: 8.625 feet: 414 WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/10/2004 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: RICHARD LACEY Company: KANSAS CORPORATION COMMIS Phone: (620) 225-8888

Proposed Plugging Method: SAND BOTTOM TO 4168' & PLACE 4 SX CMT ON TOP. FREEPOINT PIPE & PULL TO 1400'. SPOT 15 SX GEL & 50 SX CMT. PULL PIPE TO 600' & PUMP 50 SX CMT. PULL CASING TO 450' & SPOT 50 SX CMT. PULL CASING TO 40' & SPOT 10 SX CMT. RESTORE LOCATION

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/10/2004 5:00 PM KCC Agent: STEVE DURRANT

Actual Plugging Report:

PBTD 3800'. 1ST PLUG 6 SX CMT AT 3800' WITH DUMP BAILER. 2ND PLUG PULL CASING TO 1400'. PUMP 8 SX GEL WATER & 50 SX CMT. DISPLACE WITH 7 SX GEL. HOLE DID NOT CIRCULATE. 3RD PLUG PULL CASING TO 600' & PUMP 50 SX CMT. NO CIRCULATION. 4TH PLUG PULL CASING TO 450' & PUMP 50 SX CMT. NO CIRCULATION. 5TH PLUG PULL CASING TO 40' & FILL CASING TO SURFACE.


Perfs:

RECEIVED
SEP 20 2004
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2620' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Steve Durrant

(TECHNICIAN)