

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20534-00-00
Spot: E2SENE Sec/Twnshp/Rge: 19-24S-15W
3490 feet from S Section Line, 100 feet from E Section Line
Lease Name: STEWART Well #: 3
County: STAFFORD Total Vertical Depth: 700 feet

Operator License No.: 31629
Op Name: NASH OIL & GAS, INC.
Address: P. O. BOX 8747
PRATT, KS 67124

PROD Size: 5.5 feet: 700 WITH 500 SX CMT
SURF Size: 8.625 feet: 210 WITH 150 SX CMT

\$35⁰⁰

Well Type: SWD UIC Docket No: D19367.0 Date/Time to Plug: 09/08/2004 12:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: PUMP DOWN 5 1/2" WITH 100# HULLS & 60 SX CMT. PRESSURE TEST.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/08/2004 1:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 700'. 8 5/8" X 5 1/2" ANNULUS CMT TOP =6'. CHECKED WITH ROD. PUMPED DOWN 5 1/2" WITH 100# HULLS & 60 SX CMT. MAXIMUM PRESSURE 500 PSIG. SHUT IN PRESSURE 100 PSIG. WAITED 15 MINUTES PRESSURED BACK TO 500 PSIG INSTANTLY.

Perfs:

Top	Bot	Thru	Comments
505	535		


INVOICED

DATE 9-16-04
NO. 2005060535

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

Plugged through: CSG

District: 01



Signed

Richard W. Lacey
(TECHNICIAN)

RECEIVED
SEP 15 2004
KCC WICHITA

Form CCF-24