

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-20606-00-00
Spot: SWNENE Sec/Twnshp/Rge: 19-24S-15W
990 feet from N Section Line, 990 feet from E Section Line
Lease Name: STEWART Well #: 2
County: STAFFORD Total Vertical Depth: 4264 feet

Operator License No.: 31629
Op Name: NASH OIL & GAS, INC.
Address: P. O. BOX 8747
PRATT, KS 67124

PROD Size: 5.5 feet: 4258 WITH 150 SX CMT
SURF Size: 8.625 feet: 254 WITH 275 SX CMT

138⁵⁸

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/08/2004 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4130' & 5 SX CMT. PLUG AT 1000' WITH 10 SX GEL - 100# HULLS - 50 SX CMT. PLUG AT 280' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: _____
Date/Time Plugging Completed: 09/08/2004 3:45 PM

WitnessType: COMPLETE (100%)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

ANHYDRITE @ 1000'. SANDED TO 4130' & 5 SX CMT WITH DUMP BAILER.
SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1000' WITH 10 SX GEL - 100# HULLS - 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:


Top	Bot	Thru	Comments
4195	4198		
4186	4190		

INVOICED
DATE 9-16-04
2005060535

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2000' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Richard M. Lacey
(TECHNICIAN)

RECEIVED
SEP 15 2004
KCC WICHITA

Form CP-23