

6 030353

15-147-30107-00-00

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

SWNE, SEC. 29, T 4 S, R 18 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

Lease Name SUTLEY Well # 2

Operator: PETROLEUM MANAGEMENT INC.

County PHILLIPS 111.48

Name & Address BOX. H (400N. WOODLAWN, WICHITA)

Well Total Depth 3430 feet

PLAINVILLE, KANSAS 67208

Conductor Pipe: Size _____ feet

67663

Surface Casing: Size 8 5/8 feet 190

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated WELL SANDED IN AND STUCK RODS & TUBING EMERG.

Plugging Contractor HALLIBURTON CEM. License Number _____

Address OBERLIN KANSAS

Company to plug at: Hour: PM Day: 30 Month: 11 Year: 19 84

Plugging proposal received from WAYNE FUZZELL

(company name) P.M.I. (phone) _____

were: WELL FLOWED SOME - ORDER 400 SX. 50/50 PPT 6 PPT GEL 3 PPT - 3 SX. GEL - 4 SX. HULLS

PUMP DOWN 4 1/2 CASING AND - 8 5/8 ANNULUS.

WELL HAD TUBING SHOT OFF @ 2998 BUT UNSCREWED @ 2675 THEN SAND WAS

TAGGED @ 2550 - ROD FISH WAS @ 2250 - WELL WAS BEING STRIPPED

NO FLOW FROM ANNULUS - 4 1/2 FLOW CARRIED WHITE SUGAR SAND INDICATIVE OF DAKOTA.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 5 PM Day: 30 Month: 11 Year: 19 84

ACTUAL PLUGGING REPORT PUMPED DOWN 4 1/2 CASING - 3 SX. GEL + 3 SX. HULLS -

200 SX. CEM. MIX. + 1 SX. HULLS - REACHED 500# 1 BBL/MIN SHUT IN.

PUMPED DOWN 8 5/8 ANNULUS - 200 SX. CEM MIX. - REACHED 250# SHUT IN.

Plug Down @ 5 PM 11-30-84

RECEIVED STATE CORPORATION COMMISSION

DEC 10 1984

Remarks: THIS WELL HAD BEEN SQUEEZED TUBE BEFORE FOR BREAKINS (If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

NOTICED

Signed Carl Goodrow (TECHNICIAN)

DATE 12-13-84

INV. NO. 5973

12-10-84
12-7-84
14