

6 010749

3-8 15-147-30006-00-00175  
R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 12-21-64  
SE SW, SEC. 29, T 4 S, R 18 W/Exx

TECHNICIAN'S PLUGGING REPORT

Operator License # 5242

660 feet from S section line  
3300 feet from E section line

Operator: Petroleum Management Inc.  
Name & Address 14201 E. Central  
Wichita, Ks.

Lease Name Van DerWege Well # 1  
County Phillips 111.93

Well Total Depth 3444 PB 3285 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 210-

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor P.M.I. License Number 5242

Address Same

Company to plug at: Hour: 9:00AM Day: 8 Month: Mar Year: 19 91

Plugging proposal received from Don Keener

(company name) Same (phone)

were: Order 325 sks 65/35 poz 8% gel and 400 lbs. hulls.

4 1/2 casing at 3352. Perf 3105 - 3219. 4 1/2 sq 780 - 966. 871 - 902.

769 with 560 sks cement.

Plugging Proposal Received by D. F. B.  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:15AM Day: 8 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Ran tubing to 2528 pumped down 100 sks cement.

Pulled tubing to 1300. Pumped down 30 sks cement; circ. pulled tubing.

Pumped down casing 20 sks cement. Max pres. 700 closed w/300. Pumped down

8 5/8 175 sks cement w/400 lbs. hulls. Max pres. 800. Closed w/300 lbs. pres.

RECEIVED  
STATE CORPORATION COMMISSION  
3-22-91  
MAR 22 1991

Remarks: Allied cem. co.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(If  observe this plugging.)

DATE 4-2-91

INV. NO. 31294

J. S.

Signed Dale F. Balchazor  
(TECHNICIAN)  
Dale F. Balchazor