

2-20

4-041351

15-147-20036-00-00

23

R

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- -

NW NE SW /4 SEC. 29, 04 S, 18 W  
2310 feet from S section line  
3630 feet from E section line

Operator license# 5242

Lease Van Dor Wege well # 3

Operator: Petroleum Management Inc.

County Phillips

Address: 14201 E. Central  
Wichita, Kansas 67230

Well total depth 3265 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 206 feet  
w/160 sx.cmt.

106.11

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Plainville, Kansas 67663

Company to plug at: Hour: \_\_\_\_\_ Day: 20 Month: February Year: 92

Plugging proposal received from: Don Keener

Company: Petroleum Management Inc. Phone: 913-434-2042

Were: 4 1/2" casing set @ 3263'. T.D. 3265'. Perf. @ 3113' - 3138'.  
Anhy. Perf. or D.V. @ 1350'. Dakota @ 650'. W.L.M. 3138'.  
Ordered 300 sx. 60/40 poz. - 10% gel. - 600# hulls.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 13 1992

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

CONSERVATION DIV  
MAR 13 1992

Completed: Hour: 2:15P.M., Day: 20, Month: February, Year: 1992

Actual plugging report: Run in hole with perferators, perf. anhy @ 1350'  
and base dakota @ 650'. Hooked up to 4 1/2" casing pumped in 50 sx.  
cement followed with additional 150 sx. 60/40 pozmix, 10% gel. with 400#  
hulls mixed in cement. Max. 500# P.S.I. S.I. 300# P.S.I. Hooked up to  
8 5/8" S.P. Pumped in 100 sx. cement with 200# hulls mixed in cement.  
Max. P.S.I. 300#. S.I. 150#.

Remarks: Workover pits are lined.

Condition of casing(in hole): GOOD  BAD  Anhy.plug: YES  NO   
Bottom plug(in place): YES , CALC , NO  Dakota plug: YES , NO   
Plugged through TUBING , CASING . Elevation: \_\_\_\_\_ GL

INVOICED

I did  did not  observe the plugging.

Dennis L. Hamel

DATE 3-17-92

INV. NO. 34770

10

(agent)