

4-041350

2-20

25
R

E-12,729

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-147-20,300
NE /4 SEC. 29, 04 S, 18 W
2865 feet from S section line
1320 feet from E section line

Operator license# 5242 Lease Sutley-Quanz well # 1

Operator: Petroleum Management Inc. County Phillips

Address: 14201 E. Central Well total depth 3330 feet
Wichita, Kansas 67230 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 225 feet
w/100 sx.cmt.

108.22

Aband. oil well , Gas well , Input well X, SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: Plainville, Kansas 67663

Company to plug at: Hour: 9:00A.M. Day: 20 Month: February Year: 92

Plugging proposal received from: Don Keener

Company: Petroleum Management Inc. Phone: 913-434-2042

Were: 4 1/2" casing set @ 3328'. T.D. 3330'. Perf. @ 3074' - 3124'.
Anhy. Perf. or D.V. @ 1220'. Dakota @ 700'. W.L.M. 2100.
Ordered 300 sx. 60/40 poz. - 10% gel. - 600# hulls.

RECEIVED
STATE CORPORATION COMMISSION

MAR 13 1992
3-13-92
CONSERVATION DIV.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 4:15P.M., Day: 20, Month: February, Year: 1992

Actual plugging report: Run in hole with tubing to 1850'. Spot 40 sx.
cement. Pull out of hole with tubing. Wait 3 hrs. Run in hole with
perferators, top of cement @ 1222'. Shoot anhy. @ 1220' and base Dakota
@ 700'. Run in hole with tubing to 1088'. Spot 120 sx. cement w/100#
hulls to circ. cement to surface. Pull out of hole with tubing.
Squeeze 65 sx. cement w/300# hulls. Mixed in cement. Max.600#
Shut in 300# P.S.I. Hooked up to 8 5/8" annulus and squeezed 75 sx. cmt.
w/200# hulls mixed in cement. Max.400#. S.I. 200#.

RECEIVED
STATE CORPORATION COMMISSION

MAR 17 1992
CONSERVATION DIV.

Remarks: Workover pits are lined.
Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES , CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

I did / did not observe the plugging.

Dennis L. Hamel

INVOICED
DATE 3-17-92
INV. NO. 34771

HD

(agent)