

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
245 North Water
WICHITA, KANSAS 67202

Rev. 6-3-74
FORM CP-1

WELL PLUGGING APPLICATION FORM
File One Copy

API Number 15 - 147 - 20,317-000 (of this well)
Lease Owner Cherokee Petroleum Corporation
Address 410 Seventeenth Street, Suite 2300, Denver, CO 80202
Lease (Farm Name) BOHL #1 Well No. #1
Well Location C SW SE Sec. 7 Twp. 4S Rge. 18W (E) (W) 18W
County Phillips County Total Depth 3538' Field Name
Oil Well Gas Well Input Well SWD Well Rotary D & A X
Well Log attached with this application as required Yes
Date and hour plugging is desired to begin 4/03/81, 7:30 a.m.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-128 OF THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

Name of company representative authorized to be in charge of plugging operations:
Bill Craig (Toolpusher) Address 702 S. 2nd St., Hill City, KS 67642

Plugging Contractor Abercrombie Drilling, Inc. License No.
Address 801 Union Center, Wichita, KS 67202

Invoice covering assessment for plugging this well should be sent to:
Name Cherokee Petroleum Corporation

Address 410 Seventeenth Street, Suite 2300, Denver, CO 80202

and payment will be guaranteed by applicant or acting agent.

RECEIVED
STATE CORPORATION COMMISSION

Signed: Jack L. Partridge
Applicant or Acting Agent
Jack L. Partridge, Vice President
Date: April 7, 1981
APR - 8 1981
4-8-81
CONSERVATION DIVISION
Wichita, Kansas

15-147-20317-00-00

CONTRACTOR'S WELL LOG

OPERATOR:	Cherokee Petroleum Corporation
CONTRACTOR:	Abercrombie Drilling, Inc.
WELL NAME:	BOHL #1
LOCATION:	C SW SE, Section 7-4S-18W Phillips County, Kansas
SPUD DATE:	3/26/81
COMPLETION DATE:	4/03/81

0	206	Sand & Shale
206	515	Shale
515	1460	Sand & Shale
1460	1498	Anhydrite
1498	1790	Shale
1790	2105	Shale & Lime
2105	2505	Shale
2505	3082	Shale & Lime
3082	3185	Lime
3185	3235	Lime & Shale
3235	3320	Lime
3320	3435	Lime & Shale
3435	3538	Lime
	3538	Rotary Total Depth

Spud hole @ 7:30 p.m., 3/26/81. Drilled 206' in a 12 1/4" hole. Ran 5 jts. of 8 5/8" - 24# casing (tally 196.68') Set @ 205'. Cemented with 175 sx. of 60-40 posmix, 2% gel, 3% c.c. Cement did circulate. Plug was down @ 12:15 a.m., 3/27/81.

T.D. @ 3538'. Set 1st Plug @ 840' with 65 sx. Set 2nd Plug @ 210' with 30 sx. Set 3rd Plug @ 40' Solid Bridge with 10 sx., 5 sx. in rathole. 50-50 posmix, 6% gel. Cement by Halliburton. Job was complete @ 7:30 a.m., 4/03/81. State Plugger - Marion Schmidt.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jack L. Partridge, Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the BOHL #1, C SW SE, Section 7-4S-18W, Phillips County, Kansas.


ABERCROMBIE DRILLING, INC.

Jack L. Partridge
BY: Jack L. Partridge, Vice President

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 7th day of April, 1981.

2-4-85

Suzanne M. Hofer
Suzanne M. Hofer, Notary Public



RECEIVED
STATE CORPORATION COMMISSION

APR - 8 1981 4-8-81
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202

INVOICE and WELL PLUGGING AUTHORITY

May 27, 1981

INVOICE NUMBER: 5435-W

TO: Cherokee Petroleum Corp.
410 17th St.
#2300
Denver, CO. 80202

15-147-20317-00-00

PLUGGING ASSESSMENT AS FOLLOWS:

Bohl #1
C SW SE, Sec. 7-4S-18W
Phillips
Abercrombie Drilling Co., Inc.

\$114.99

NOTE: We also need the following before our file is completed:

- _____ Well Plugging Record (CP-4)
- _____ Well Log
- _____ Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.

PAYABLE UPON RECEIPT

For Administrator



Mr. Marion Schmidt, 2104 Canterbury Rd., Hays, KS., 67601
is hereby assigned to supervise the plugging of the above mentioned well.

RETURN PINK COPY WITH REMITTANCE