

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
500 INSURANCE BUILDING  
212 NORTH MARKET  
WICHITA, KANSAS 67202

FORM CP-1

WELL PLUGGING APPLICATION FORM  
File One Copy

Lease Owner Phillips Oil Operating Co.

15-147-00443-00-00

Address Box 706 Enid, Oklahoma 73701

Lease (Farm Name) Meyer Well No. #1

Well Location C SE SW Sec. 7 Twp. 4 Rge. 18 (E) X (W) X

County Phillips Field Name (If Any) \_\_\_\_\_

Total Depth 3310' Oil Well x Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Well Log filed with application Yes or Well Log filed with Plugging Supervisor \_\_\_\_\_

Date and hour plugging is desired to begin At once

Plugging of the well will be done in accordance with the Rules and Regulations of the State Corporation Commission.

Name of company representative in charge of plugging operations \_\_\_\_\_

Boyd D. Phillips

Address Enid, Oklahoma

Plugging Contractor Southwest Casing Pulling Co. License No. 399

Address Box 364 Great Bend, Kansas 67530

Invoice covering assessment for plugging this well should be sent to \_\_\_\_\_

Phillips Oil Operating Co.

Address Box 706 Enid, Oklahoma

and payment will be guaranteed by applicant.

Southwest Casing Pulling Co

Signed: S. D. Miller  
Applicant or Acting Agent

RECEIVED  
STATE CORPORATION COMMISSION

JUN 24 1975

Date: June 23, 1975

CONSERVATION DIVISION  
Wichita, Kansas

6-24-75



15-147-00443-00-00

K. T. WOODMAN PETROLEUM GEOLOGIST  
WICHITA 3, KANSAS

June 18, 1962

Sam P. Wallingford, Inc.  
304 Colorado Derby Building  
Wichita 1, Kansas

Re: Wallingford, Inc. #1 Meyer  
C SE SW 7-4-18W, Phillips County, Kansas

Gentlemen:

I have examined samples from 3000' to the total rotary depth of 3310'. The following tops have been corrected to rotary bushing measurements:

Elevation	1948 RB		Toronto	3146	-1198
Anhydrite	1505	443	Lansing	3156	-1208
Heebner	3115	-1167			

The #1 Meyer was spudded 6-10-62. 8 5/8" was set at 160' with 120 sacks cement. 5 1/2" casing was set at 3305', 6-15-62, with 85 sacks cement. The #1 Meyer was 2' lower than the #1 Bredemeier, diagonal southeast offset.

The "A" zone had a small show of oil and was slightly fossiliferous from 3156-60. The "B" zone was fine grained with good saturation and odor from 3190-94. The "D" zone had slight staining from 3229-31. The "E" zone had slight staining from 3239-43. The "F" zone had scattered stain with poor porosity from 3249-55. The "H" zone had poor porosity with slight stain and a small amount of free oil from 3304-07.

A drill stem test was attempted from 3150-3256. The packer failed, however, and a positive drill stem test was taken from 3162-3256. The tool was open 1 hour with a fair blow throughout. The test recovered 110' of slightly oil cut mud with a 15 minute BHP of 741#. IFP was 10#. FFP was 15#. This test covered the "B", "D", "E" and "F" zones. 5 1/2" casing was set on top of the "H" zone.

It is recommended that the test be drilled out to the total rotary depth and acidized in the "H" zone. After a Gamma Ray Neutron log is run, it will then be decided which zones should be perforated and selectivity acidized.

A condensed copy of the time log from 3100' to the total rotary depth is attached.

Respectfully submitted,

*K. T. Woodman*

K. T. WOODMAN

KTW/fs

RECEIVED  
STATE CORPORATION COMMISSION

JUN 24 1975

CONSERVATION DIVISION  
Wichita, Kansas

15-147-00443-00-00

June 25, 1975

Re: Meyer Well No. 1  
C SE SW 7-4-18W  
Phillips County

Phillips Oil Operating Company  
Box 706  
Enid, Oklahoma 73701

Gentlemen:

Please find attached a copy of the well plugging application filed by Southwest Casing Pulling, Great Bend, Kansas, for the above captioned well. In checking our records, we believe it should be Township 4 South, instead of 14.

We have issued a corrected authority for Township 4 South, which is attached. If this is not correct, please let us know.

Very truly yours,

---

PLUGGING DEPARTMENT  
Judy Esau

Encls.

State of Kansas



15-147-00443-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

June 25, 1975

**CORRECTED AUTHORITY**  
Original issued 6/24/75

**WELL PLUGGING AUTHORITY**

Well No.	1
Lease	Meyer
Description	C SE SW 7-4-18W
County	Phillips
Total Depth	3310'
Plugging Contractor	Southwest Casing Pulling


Phillips Oil Operating Company  
Box 706  
Enid, Oklahoma 73701

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after 90 days from the above date.

Yours very truly,

  
J. Lewis Brock, Administrator

Mr. Leo Massey, P. O. Box 582, Hays, Kansas  
is hereby assigned to supervise the plugging of the above named well.